

Enquiries: Clayton Forbes
Direct 07 5433 2543
Our Ref: DA/2024/4845
Your Ref: M2584E5

Date: 3 January 2025

DFC (Project Management) Pty Ltd, c/- JFP Urban Consultants Pty Ltd PO Box 3634 SOUTH BRISBANE QLD 4101

Dear Applicant,

Re: DEVELOPMENT APPROVAL

Planning Act 2016

Development Application No.: DA/2024/4845

Property Location: Lot 800 Flinders Street D'AGUILAR

Property Description: Lot 800 SP 331595

Development Type: Operational Works - Development Permit for

Earthworks, Roadworks & Stormwater

Please be advised that on 2 January 2025 the above development application was approved by Council's Delegate as the Assessment Manager in accordance with section 63 of the *Planning Act 2016* subject to conditions.

The following type of approval has been issued:

Development Permit - Operational Works for Earthworks, Roadworks & Stormwater

The development allowed by this approval must be carried out in accordance with the attached Decision package.

Attached is an extract from the *Planning Act 2016* which details your appeal rights and the appeal rights of any submitters, if applicable, regarding this decision.

Should you require any further information about this matter, please contact Clayton Forbes as referenced above.

Yours faithfully

Clayton Forbes
Senior Engineer

Development Services

Enclosures: Attachment 1 - Decision Notice

Attachment 2 - Assessment Manager Conditions
Attachment 3 - Approved Plans / Documents
Attachment 4 - Appeal Rights

ATTACHMENT 1

Decision Notice

Decision Notice Planning Act 2016, section 63

APPL	ICA	TIO	N	DEI	ΓΛΙΙ	C
AFFL	JUA		I		М	_0

Application No: DA/2024/4845

Applicant: DFC (Project Management) Pty Ltd,

Street Address: Lot 800 Flinders Street D'AGUILAR

Real Property Description: Lot 800 SP 331595

Planning Scheme: Moreton Bay Regional Council Planning Scheme

APPROVAL DETAILS

Date of Decision: 2 January 2025

The development application was approved by Council's Delegate as the Assessment Manager subject to conditions (refer Attachment 2).

Application Type	Development Permit	Preliminary Approval
Operational Works for Earthworks, Roadworks & Stormwater	\square	

OTHER NECESSARY PERMITS

Not applicable.

In addition to this approval, you may also be required to obtain a water approval from the Northern SEQ Distributor Retailer, trading as Unitywater. To engage a Registered Certifier to lodge your connection application, go to Unitywater's website www.unitywater.com/certifier

CURRENCY PERIOD OF APPROVAL

The currency period stated in section 85 of the *Planning Act 2016* applies to this approval as outlined below:

Operational Works - 2 years from the date of this approval starts to have effect.

DEEMED APPROVAL

Not applicable.

VARIATION APPROVAL

Not applicable.

INFRASTRUCTURE

Unless otherwise specified, all assessment manager conditions of this development approval relating to the provision of infrastructure are non-trunk infrastructure conditions under Chapter 4, section 145 of the *Planning Act 2016*.

ASSESSMENT MANAGER CONDITIONS

The Conditions relevant to this development approval are listed in Attachment 2 of the Decision package.

APPROVED PLANS / DOCUMENTS

The approved plans and/or documents as listed below for this development approval are included in Attachment 3 of the Decision package.

The approved plans/documents for this development approval are listed below.

Approved Plans and Documents			
Plan / Document Name	Reference Number	Prepared By	Dated
Cover Sheet	M2584E_5	JFP	
Construction Staging Plan	M2584E_5 LO1 C	JFP	18/11/2024
Earthworks Layout Plan - Sheet 1 of 2	M2584E_5 EW01 E	JFP	21/10/2024
Earthworks Layout Plan - Sheet 2 of 2	M2584E_5 EW02 H	JFP	13/12/2024
Earthworks Details Layout Plan- Sheet 1 of 4	M2584E_5 EW03 E	JFP	21/10/2024
Earthworks Details Layout Plan- Sheet 2 of 4	M2584E_5 EW04 E	JFP	21/10/2024
Earthworks Details Layout Plan- Sheet 3 of 4	M2584E_5 EW05 H	JFP	18/11/2024
Earthworks Details Layout Plan- Sheet 4 of 4	M2584E_5 EW06 H	JFP	13/12/2024
Earthworks Details & Notes Plan Sheet 1 of 2	M2584E_5 EW07 D	JFP	21/10/2024
Earthworks Bioretention Basin 4 Layout Plan & Details	M2584E_5 EW08 F	JFP	13/12/2024
Earthworks Bioretention Layout Plan & Details	M2584E_5 EW08B A	JFP	13/12/2024
Earthworks Bioretention Basin 3 Layout Plan & Details	M2584E_5 EW09 C	JFP	29/10/2024
Earthworks Details & Notes Plan Sheet 2 of 2	M2584E_5 EW10 B	JFP	21/10/2024
Roadworks Notes and Details Plan	M2584E_5 R03 B	JFP	21/10/2024
Roadworks Intersection Details Plan - Sheet 2 of 2	M2584E_5 R05 C	JFP	13/12/2024
Roadworks Longitudinal Sections - Road 3 (Flinders Street)	M2584E_15 R06 B	JFP	21/10/2024

Approved Plans and Documents			
Plan / Document Name	Reference Number	Prepared By	Dated
Roadworks Cross Sections - Road 3(Flinders Street)-Sheet 2 of 2	M2584E_5 R08 B	JFP	Undated
Roadworks Longitudinal Sections - Road 7 (Bushman Court)	M2584E_5 R09 A	JFP	Undated
Signs and Linemarking Plan - Sheet 1 of 2	M2584E_5 SL01 C	JFP	18/11/2024
Signs and Linemarking Plan - Sheet 2 of 2	M2584E_5 SL02 D	JFP	13/12/2024
Drainage Catchment Plan	M2584E_5 D01 D	JFP	13/12/2024
Drainage Layout Plan - Sheet 1 of 2	M2584E_5 D02 B	JFP	21/10/2024
Drainage Layout Plan - Sheet 2 of 2	M2584E_5 D03 E	JFP	13/12/2024
Drainage Longitudinal Sections Line M,3M, N,1A-7M & 1B-7M	M2584E_5 D04 B	JFP	21/10/2024
Drainage Longitudinal Sections Line 0,1A-20 &J	M2584E_5 D05 C	JFP	29/10/2024
Drainage Calculations Table Sheet 1 of 2	M2584E_5 D06 B	JFP	21/10/2024
Drainage Calculations Table Sheet 2 of 2	M2584E_5 D07 B	JFP	21/10/2024
Drainage Structure Details Sheet 1 of 2	M2584E_5 D08A B	JFP	21/10/2024
Drainage Structure Details Sheet 2 of 2	M2584E_5 D08B A	JFP	12/13/2024
Bioretention Plan & Details - Basin 3	M2584E_5 D09 C	JFP	13/12/2024
Bioretention 3 Sediment Forebay 1 Plan & Sections	M2584E_5 D10 B	JFP	29/10/2024
Bioretention 3 Sediment Forebay 2 Plan & Sections	M2584E_5 D11 B	JFP	29/10/2024
Bioretention Plan & Details - Basin 4	M2584E_5 D12 D	JFP	13/12/2024
Bioretention 4 Sediment Forebay Plan & Sections	M2584E_5 D13 D	JFP	13/12/2024

Plans and Documents to be Amended			
Plan / Document Name	Reference Number	Prepared By	Dated
Roadworks Layout Plan - Sheet 1 of 2	M2584E_5 R01 B	JFP	21/10/2024
Roadworks Layout Plan - Sheet 2 of 2	M2584E_5 R02 D	JFP	18/11/2024
Roadworks Intersection Details Plan - Sheet 1 of 2	M2584E_5 R04 D	JFP	18/11/2024
Roadworks Cross Sections - Road 3(Flinders Street)-Sheet 1 of 2	M2584E_5 R07 B	JFP	Undated
Roadworks Cross Sections - Road 7(Bushman Court)	M2584E_5 R10 B	JFP	Undated

ASSESSMENT BENCHMARKS

The Assessment Benchmarks that applied to the development from the following Categorising Instruments include;

Categorising Instrument (Planning Regulation 2017)

State Planning Policy

• State Planning Policy 2017, Part E.

Regional Plan

South East Queensland Regional Plan 2017 (ShapingSEQ).

Local Categorising Instrument (Moreton Bay Regional Planning Scheme)

• MBRC Planning Scheme - Works Code

Local Categorising Instrument (Variation Approval)

Not applicable.

Local Categorising Instrument (Temporary Local Planning Instrument)

Not applicable.

OTHER RELEVANT ASSESSMENT MATTERS

Not applicable.

REASONS FOR THE DECISION

Not Applicable.

REASONS FOR APPROVAL DESPITE NON-COMPLIANCE WITH ASSESSMENT BENCHMARKS

Not applicable.

REFERRAL AGENCY CONDITIONS

There were no Referral Agencies applicable to this development application.

SUBMISSIONS

Not applicable.

APPEAL RIGHTS

Attachment 4 of the Decision package is an extract from the *Planning Act 2016* which details your appeal rights, and the appeal rights of any submitters, if applicable, regarding this decision.

ATTACHMENT 2 Assessment Manager Conditions of Approval

CONDITION		TIMING
OPERA	ATIONAL WORKS	
1	Retaining Wall Location	
	Type A2 and A5 retaining walls within Lots 121-123 & 126-128 where fronting onto Road or Drainage Reserve are to be full located within the respective lot.	Prior to requesting an On Maintenance inspection.
2	Road Classifications for Pavement Design	
	Design pavement in accordance with the following road classifications:	Prior to subgrade inspections.
	Road 3 - Living Residential Road - 1.2x10 ⁵ ESA	
	Road 7 - Living Residential Road - 1.2x10 ⁵ ESA	
3	Amendments Required	
	The following amendments must be completed and submitted for approval by Council's delegated officer: 1. Remove the inconsistencies between the Road 3 and Road 7 Roadworks Cross Sections plans indicating Steel Beam Guardrails and the corresponding Roadworks Layout Plans indicating Hardwood Timber Vehicle Barriers. The amended Roadwork Layout Plans are to detail the extent of the Steel Beam Guardrails having consideration for the extent of the adjacent hazard. The submission is to include a copy of the hazard assessment undertaken in accordance with Austroads Guide to Road Design Part 6 to determine the proposed barrier. The design drawings must approved by Council's delegated officer. Provide a complete set of all drawings to Council.	Prior to a prestart meeting being held.
4	Approved Plans and/or Documents	
	Undertake development generally in accordance with the approved plans and/or documents. These plans and/or documents will form part of the approval, unless otherwise amended by conditions of this approval.	At all times during construction and prior to works being accepted Off Maintenance.
5	Errors and Omissions	
	Where errors or omissions occur in the design or works do not conform to or meet Council standards then these works shall be rectified to comply with Council standards at no cost to Council.	At all times during construction and prior to works being accepted Off Maintenance.
	Where drawings contain insufficient detail or do not contain details of works that are either necessary or associated with the development then these works shall be designed and constructed to Council standards.	
	Only the approved plans shall be used for construction.	

CONDI	TION	TIMING
	Note: Council reserves the right to amend the approved drawings or request further information should this become necessary.	
6	Works – Applicant's Expense	
	All works, services, facilities and/or public utility alterations required by or as a consequence of this approval or stated condition/s, whether carried out by the Council or otherwise, shall be at the developer's expense unless otherwise specified or agreed in writing.	At all times during construction and prior to works being accepted Off Maintenance.
	Replace existing Council infrastructure (including but not limited to street trees and footpaths) to Council's standards.	
7	As Constructed Drawings	
A	Provide, for review and approval, Council with a preliminary set of the surveyor and engineering As Constructed drawings for the approved works and a digital ADAC file.	Prior to requesting an On Maintenance inspection.
	Note: The current design standard and relevant planning scheme policy is MBRC Planning Scheme Policy Operational Works inspection, maintenance and bonding procedures.	
В	Submit 'As Constructed' drawings and digital ADAC file in accordance with Council's Planning Scheme, relevant Planning Scheme Policies and design standards current at the time of development.	Prior to works being accepted On Maintenance.
8	Works in Existing Roads	
A	Works carried out in or affecting existing Roads must be undertaken so that these roads are maintained in a safe and useable condition.	At all times.
В	Provide to Council's delegated officer and receive acknowledgement of a Traffic Management Plan, with site specific Guidance Scheme, prepared and signed by an appropriately qualified person and in accordance with the Manual of Uniform Traffic Control Devices (MUTCD) for any works that will affect traffic movements or traffic safety in existing roads.	At least five (5) days prior to undertaking the works in or affecting existing roads.
	 A 'Part Road Closure Application' for Development Works form is to accompany the Traffic Management Plan submission. This submission is required to be made in addition to any Traffic Management Plan which has been submitted and/or approved as part of a Construction Management Plan for the site during the development application process for Material Change of Use or 	

COND	TION	TIMING
	Reconfiguring a Lot or subsequent non-IDAS applications.	
9	Information Sign – Works in Existing Roads	
	A construction advisory road sign must be erected and regularly updated and maintained displaying the developer and contractors details and the expected completion date for works on existing roads. The sign shall be located so as be clearly legible to the public from of minimum 15m distance from the existing road on which the works are to be carried out on.	For the duration of the works from commencement to acceptance of On Maintenance.
10	Information Sign – Development Works	
	An information sign containing the following details and after hours contact details must be provided at each entrance to the development site: Developer Supervising Consultant/ Engineers / Project Manager Principal Contractor	For the duration of the development works from commencement to acceptance On Maintenance by Council.
	The sign must be at least 0.9m (W) by 0.6m (H). The sign must be erected and maintained for the duration of the development works.	
11	Prestart Meeting	
	Arrange a prestart meeting with Council officers from Development Engineering section (Email - Council@moretonbay.qld.gov.au - Attention - Development Services - Engineering North - DA/2024/4845 The following people will be required to attend the	Not less than 7 days prior to commencing any construction works.
	prestart meeting: Developer's Supervising Engineer Contractor's Engineer / Project Manager Contractor's Site Supervisor Fauna Manager (where required).	
12	Mandatory Inspections with Council Officers	
	Submit required documentation for each mandatory inspection in accordance with MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to requesting inspection.
	Undertake the following inspections with Council's delegated officer (where applicable to approved works) in accordance with MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures:	As prescribed below.
Α	Stormwater drainage.	Prior to backfilling stormwater trenches.

CONDI	TION	TIMING
В	Subgrade / box inspection.	Prior to placement of structural pavements.
С	Preseal inspection.	Prior to priming and sealing of structural pavements.
D	For concrete slabs and concrete pavements - foundations / subgrade and pre-pour inspections.	Prior to concrete pouring.
E	On maintenance inspection for Council's acceptance of all works.	Prior to works being accepted On Maintenance.
F	Off maintenance inspection of all works.	After maintenance period has elapsed.
	Note: Reinspections attract a fee in accordance with Council's Fee Schedule. The fee must be paid prior to the reinspection.	Ciapoca.
G	Provide Council's delegated officer with a copy of an Engineers' Certificate Soil tester's reports demonstrating that required compaction standards, finished levels and textures of finish have been obtained in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to proceeding to construction of next layer or surfacing.
13	Testing Frequency – General	
A	All testing of the works shall be carried to comply with the minimum testing frequencies given in MBRC Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	At all times during construction.
	Note: Council's delegated officer may vary the frequency of testing to suit site conditions but must provide written advice to the supervising engineer prior to commencement of the relevant works.	
В	Provide a plan identifying locations where testing has occurred.	Prior to works being accepted On Maintenance.
14	Construction Hours Restrictions	
	Ensure hours of construction are limited to 0630 to 1830 Monday to Saturday and not at all on Sundays and public holidays.	At all times.
	Note: Council's engineer may approve (in writing) work outside the above hours where it can be demonstrated to the satisfaction of Council that the work will not cause unreasonable interference with the amenity of adjoining premise and any person.	
15	Construction Nuisance and Annoyance	
	Ensure construction works do not cause unreasonable interference with the amenity of adjoining premise and any person by reason of noise, vibration, electrical interference, smell, fumes, vapour, steam, soot, ash,	At all times.

CONI	DITION	TIMING
	dust, silt, wastewater, waste products, grit, oil or otherwise.	
16	Construction Site Management	
	Ensure the construction site is kept in a clean and tidy state.	At all times.
	A Implement an Erosion and Sediment Control Plan which is prepared by an experienced Certified Professional in Erosion and Sediment Control (CPESC) in accordance with International Erosion Control Association Australasia (IECA) Best Practice and Sediment Control document and MBRC Planning Scheme current at the time of development.	Prior to commencement of works and to be maintained current at all times during construction and until the development is accepted offmaintenance.
	B The temporary erosion and sediment control measures shall be maintained and be functional until the end of the Maintenance Period for the works or earlier if Council's delegated officer considers they are no longer required.	At all times during construction.
	Note: Council's delegated officer may order additional measures to control silt on site at no cost to Council.	
17	Spillage onto Existing Roads	
	Clean those parts of the access route to the site that are affected by any material dropped, deposited or spilled on the roads as a result of construction processes associated with the site.	At all times during construction.
	 Note: All materials must be swept up and removed from the roads and not directed into Council's stormwater drainage system. All care must be taken to prevent sediments being deposited on roads. 	
18	Dust Control – Nuisance and Annoyance	
	Implement suitable dust control measures. If airborne particles are observed leaving the site, any work is to cease immediately and satisfactory dust suppression is to be implemented.	At all times prior to works being accepted Off Maintenance.
	Note: Dust suppression measures must be in place at all times including weekends and public holidays.	
19	Earthworks Batters	
	Where approved drawings do not include specifications for scour and erosion protection apply the following treatments to batter slopes: • Slopes of 1:6 or flatter – topsoil and seed • Slopes between 1:6 and 1:4 – topsoil and turf • Slopes of 1:4 or greater – provide treatment recommendation from a qualified geotechnical	At all times during construction.

CONDI	TION	TIMING
	engineer (RPEQ.) for Council approval prior to undertaking batter works Or as directed by Council.	
	Note: Batters within Open and Civic Spaces are to be treated in accordance with MBRC Planning Scheme Policy Integrated Design - Open and Civil Space Design.	
20	Earth Retaining Structures	
A	Design and construct all earth retaining structures in accordance with: • Council's Planning Scheme and relevant Planning Scheme Policies; • Relevant Australian Standards; and • Relevant Building Code requirements.	At all times.
	The minimum design life (the period assumed in design for which a structure or structural element is required to perform its intended purpose without replacement or major structural repairs) for the earth retaining structure that is specified in Table 3.1 of Australian Standard AS4678. Note: Timber retaining structures and bolder retaining walls are not accepted unless specifically approved in writing by Council.	
В	Provide written certification from a suitably qualified and experienced RPEQ that the works comply with this permit condition.	Prior to works being accepted On Maintenance.
21	Unsuitable Fill Materials	
	 Ensure that all fill material used on the development site is free of unsuitable materials, identified in AS3798 and the following: actual acid sulfate soils and potential acid sulfate soils; organic or putrescible matter; material imported from land which is, or has been, listed on the "Environmental Management Register" under the Environmental Protection Act 1994; and building demolition material. 	At all times.
22	Compaction Requirements	
	All fill material which is intended to be load bearing, or the finished surface level of which is required to remain approximately constant, is selected, placed and compacted to the standard prescribed in Australian Standard AS3798 Guidelines on Earthworks for Commercial and Residential developments.	At all times during construction.
23	Pavement Design	
A	All road pavements must be designed, constructed and tested in accordance with MBRC Planning Scheme Policy - Integrated Design - Street, Roads and Utilities	At all times during construction.

CON	CONDITION		TIMING
		 and standard drawings current at the time of construction. Note: Council requires a primer seal placed under all asphalt surfaces. Increased asphalt surface thicknesses for road thresholds are to be identified in the pavement design. 	
	В	Submit, for review and approval by Council's delegated officer, a pavement design for all roads. Pavement designs are to include Soil tester's reports.	Prior to subgrade inspection.
24		Pavement Jointing Detail	
		Undertake pavement jointing in accordance with IPWEA. Standard Drawings RS-170.	Prior to works being accepted On Maintenance
25		Road Thresholds	
		Design and construct road threshold treatments in accordance with Council's Planning Scheme Policy Integrated Design - Streets, Roads and Utilities, standard drawings current at the time of construction and the following requirements: • Urban areas only: Concrete threshold treatment - full depth colour batched concrete. • All areas: Streetprint/indented/stamped asphalt treatment - an additional 10mm asphalt depth to be applied to the total area of threshold. Increased asphalt depth to be identified in Pavement Design	At all times.
		Submit, for review and approval by Council's delegated officer, the proposed colours and surface patterns for all road thresholds. Note: Road threshold colours are to be bright and natural and able to withstand continuous traffic use without discolouration.	At least 7 days prior to commencing construction of thresholds.
26		Concrete Footpaths	
		Construct concrete footpaths and kerb ramps in accordance with IPWEA Standard Drawings RS-065 and RS-093.	Prior to works being accepted On Maintenance.
27		Street Signs	
		Street signs must be provided in accordance with Council's Standard Drawings and IPWEA Standard Drawings. Note: House numbers required for these signs shall be obtained from Council's house numbering officer by contacting Council's Customer Service. The MBRC Logo is not to be put on the sign.	Prior to works being accepted On Maintenance.

CON	IDI.	TION	TIMING
28		Stormwater Pipe Outlets and Culvert Inlets and Outlets	
		Stabilise all culvert inlets and outlets or stormwater drainage outlets in accordance with industry best practice and the following requirements: Rock gabion baskets/rock mattresses Grouted rock/stone pitching with a properly designed and prepared base and constructed to the following requirements: Mortar to be 1 part cement to 3 parts sand (by volume). Open face stone pitching is to be used where the concrete is recessed 50mm behind the stone facing. Select spalls to avoid sharp edges. Other solutions as approved by Council's delegated officer. Note: Dumped rock is generally not considered as an appropriate solution.	At all times.
29		Stormwater Overland Flow – Site Earthworks	
		 Earthworks must be undertaken on the site so as not to cause nuisance and annoyance to any person or premises. The development must: Allow stormwater overland flow which entered the land prior to the commencement of the earthworks to continue to enter the land; and Ensure stormwater overland flow from the development site is not discharged or diverted onto land (other than a road) adjacent to the site in a manner which: concentrates the rate of flow at any point along the property boundary; or increases the peak flow rates of stormwater discharged at any point along the property boundary; beyond that which existed prior to commencement of these earthworks. 	At all times during construction.
30		CCTV – Stormwater Pipes	
	A	Provide a high definition Closed Circuit Television (CCTV) recording of all stormwater pipes including inter allotment roofwater drainage. CCTV to clearly display all joints (full surrounds) and any form of damage or defects. The recording is to include a report signed by an R.P.E.Q. stating that the recording has been reviewed and all works are satisfactory. Where defects have been identified, consultant is to provide method of rectification to Council for approval, prior to carrying out any rectification works.	At least 7 days prior to the On Maintenance inspection.

CONI	DITION	TIMING		
	B Undertake and provide, to the satisfaction of the Council, a high definition Closed Circuit Television (CCTV) recording of all stormwater pipes, including inter allotment roof water drainage. Recording to be undertaken within one month immediately preceding making a request for Off Maintenance inspection. CCTV to clearly display all joints (full surrounds) and any form of damage or defects, including date and time of the recording.	Prior to a request for Off Maintenance inspection.		
	The recording is to include a report signed by a suitably qualified Registered Professional Engineer Queensland (RPEQ) stating that the recording has been reviewed and all works are satisfactory.			
	Where defects have been identified, consultant is to provide method of rectification to Council for approval, prior to carrying out any rectification works.			
31	Drainage Behind Retaining Walls			
	Design and install agricultural pipes or strip drains behind retaining walls in accordance with Q.U.D.M. to connect to: • The proposed inter-allotment drainage systems; or • To drainage inlet structures via a stub connection in roadways; or • Directly to kerb and channel if there are no drainage structures within 10m of the frontage of the land; or • As approved in writing by Council's delegated officer. Notes: • Corrugated pipes are not to be used to connect the	Prior to works being accepted On Maintenance.		
	 stormwater drainage to Council's infrastructure. The drainage system behind retaining walls must not connect to Council's subsurface drainage system in the Council road. 			
32	Provision of Kerb Adapters			
	Provide a minimum of two (2) metal kerb adaptors per lot for lots that drain to the road. Where a lot has side crossfall of up to 1.5%, one (1) kerb adaptor shall be located at each side of the lot. Where a lot has side crossfall of greater than 1.5%, both kerb adaptors shall be located at the low side of the lot.	Prior to works being accepted On Maintenance.		
	For lots with a concrete footpath at the frontage, the kerb adaptors shall be connected to the front boundary of the lot with Class SN8 uPVC stormwater pipe.			
33	Certification – Public Stormwater Management Infrastructure			
	Provide documentation to Council from a Registered Professional Engineer (RPEQ) specialising in stormwater design certifying that the stormwater management	Prior to works being accepted On Maintenance.		

CON	DI	TION	TIMING
		treatment train as approved in the stormwater management plan and design drawings has been constructed in accordance with engineering best practise and is functioning as designed.	
		The certification shall include the completed sign-off forms for bioretention systems prepared by Water by Design in Partnership with Healthy Waterways shall be completed. The sign-off forms are accessible from www.waterbydesign.com.au .	
34		Public Bioretention Inspections	
		Provide Council with notice of the subsoil drains being laid and the filter media being installed. Note: Council's delegated officer may attend the	Not less than 48 hours prior to subsoil drains being laid and the filter media being installed.
		inspection.	
35		Maintenance Process for Public Bioretention Basin	
	Α	The entire bioretention basin shall act as a sediment basin.	During the build-out phase (80%) or up to a maximum of two (2) years.
		Note: Council will consider alternative solutions to achieve the desired outcome.	
	В	Submit, for review and approval by Council's delegated officer, a deferred works schedule to cover the cost of basin conversion plus twenty-five percent (25%) and in accordance with the requirements of Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Prior to the bioretention basin area being accepted On Maintenance as a sediment basin.
		 The following works are to be included as a minimum in the deferred works bond schedule: removal of sacrificial turf and geofabric; and In-situ hydraulic conductivity testing of filter material in accordance with the "Guidelines for Soil Filter Media in Bioretention Systems: (produced by the Faculty for Advanced Water Biofiltration) requirements. Planting out of the basin in accordance with the approved landscaping drawings. 	
	С	Construct deferred works and any other works necessary to convert to the basin from sediment basin to a functioning bioretention basin in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures.	Once the contributing catchment achieves eighty percent (80%) build-out or a maximum of 2 years.
		In-situ hydraulic conductivity testing of filter material is to be provided to Council's delegated officer to demonstrate that area can be planted out. Where in-situ hydraulic conductivity testing shows that the filter material is not acceptable then replacement of the filter material is required in addition to planting out of basin area.	

CONDITION	TIMING
Note: Deferred Works for bioretention basin conversion are subject to a separate on maintenance process to the other civil works for the development. The On Maintenance process is to be in accordance with Council's Planning Scheme Policy - Operational Works inspection, maintenance and bonding procedures including on and off maintenance inspections and maintenance period.	

ADVICES Development Permit This approval shall comply with all the conditions of related approval as stipulated in Council's Decision Notice – Development Permit dated 18 September 2024 referenced as **DA/2024/2888**. The Applicant needs to be aware that the Currency Period of that Decision Notice may determine the validity period of this Decision Notice. 2 **Extent of Checking by Council** This approval shall not be taken to mean that the drawings have been checked in detail and Council accepts no responsibility whatsoever for the survey information, the design, or for the accuracy of any information or detail contained in the approved drawings and specifications. 3 Aboriginal Cultural Heritage Act The Aboriginal Cultural Heritage Act 2003 commenced in Queensland on April 16, 2004. Under the Act, indigenous parties are key in assessing cultural heritage significance. The Aboriginal Cultural Heritage Act 2003 establishes a Duty of Care for indigenous cultural heritage. This applies on all land and water, including freehold land. The Cultural Heritage Duty of Care lies with the person or entity conducting the activity. Penalty provisions apply for failing to fulfil the Cultural Heritage Duty of Care. Those proposing an activity that involves additional surface disturbance beyond that which has already occurred on the proposed site need to be mindful of the Duty of Care requirement. Details of how to fulfil the Duty of Care are outlined in the Duty of Care Guidelines gazetted with the Act. Council strongly advises that you contact the relevant state agency to obtain a copy of the Duty of Care Guidelines and further information on the responsibilities of developer under the terms of the Aboriginal Cultural Heritage Act 2003. **Environmental Protection Act** It remains the duty of care of the site owner not to cause Environmental Harm as defined under the Environmental Protection Act 1994. 5 **Biosecurity Act 2014 - Fire Ant Control** Significant portions of the Moreton Bay are within Fire Ant Biosecurity Zone 2 and must remain vigilant for the presence of fire ants. Under the Biosecurity Act 2014, individuals and businesses are responsible for ensuring that they follow the movement controls for specific organic materials to help prevent the spread of fire ants within South East Queensland's fire ant biosecurity zones. Movement of a fire ant carrier from within the fire ant biosecurity zone may need a biosecurity instrument permit. More information is available on https://www.fireants.org.au/treat/business-andindustry/movement-controls

ATTACHMENT 3

Approved Plans / Documents

OPERATIONAL WORKS CIVIL ENGINEERING

PROJECT DETAILS:

'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR

PROJECT NUMBER: M2584E_5
MORETON BAY REGIONAL COUNCIL

REFERENCE: DA/2024/2888

35 ALLOTMENTS LOT 1 & 2 ON RP230991 & RP80309 AREA - 5.722 ha

LOCALITY PLAN



CITY OF MORETON BAY

SAFETY IN DESIGN

THE ENGINEERING DESIGN FOR THE PROPOSAL HAS BEEN DEVELOPED TO MEET THE STATED PROJECT BRIEF, AS EXPRESSED IN JFP URBAN CONSULTANTS OFFER FOR THE WORKS, AND THE DESIGN STANDARDS STIPULATED BY THE LOCAL AUTHORITY NAMED ON THIS PLAN. IT IS EXPECTED THAT A COMPETENT PRINCIPAL CONTRACTOR WILL BE APPOINTED FOR THE PROJECT AND THAT ALL 'HIGH RISK' CONSTRUCTION WORKS WILL BE ADDRESSED AS PART OF THEIR PROJECT SAFETY PLAN FOR THE SITE.

NON-STANDARD DESIGN SOLUTIONS ADOPTED IN THE PREPARATION OF THE PROPOSAL ARE LISTED AS FOLLOWS:

THERE ARE NO NON-STANDARD DESIGN ITEMS TO LIST

SEWERAGE PLANS

	_ \/	701	LILANS
M2584E_5	S01	С	SEWERAGE LAYOUT PLAN
M2584E_5	S02	С	SEWERAGE DETAILS LAYOUT PLAN
M2584E_5	S03	Α	SEWERAGE DETAILS PLAN
M2584E_5	S04	С	SEWERAGE NOTES PLAN
M2584E_5	S05	D	SEWERAGE LONGITUDINAL SECTIONS LINE 7, 10, 5-7, 4-7, 3-7 &
M2584E_5	S06	С	LPS - SEWERAGE LAYOUT PLAN
M2584E_5	S07	С	LPS - SEWERAGE DETAILS LAYOUT PLAN - SHEET 1 of 3
M2584E_5	S08	С	LPS - SEWERAGE DETAILS LAYOUT PLAN - SHEET 2 of 3
M2584E_5	S09	С	LPS - SEWERAGE DETAILS LAYOUT PLAN - SHEET 3 of 3
M2584E_5	S10	Α	LPS - SEWERAGE NOTES PLAN
M2584E_5	S11	С	LPS - SEWERAGE LONGITUDINAL SECTIONS LINE A & B
W/AT	FR	RF	TICULATION PLANS
**/ \	,	. , L	

M2584E_5	W01	С	WATER RETICULATION LAYOUT PLAN - SHEET 1 of 4
M2584E_5	W02	В	WATER RETICULATION LAYOUT PLAN - SHEET 2 of 4
M2584E_5	W03	В	WATER RETICULATION LAYOUT PLAN - SHEET 3 of 4
M2584E_5	W04	В	WATER RETICULATION LAYOUT PLAN - SHEET 4 of 4
M2584F 5	W/05	R	WATER RETICULATION DETAILS

M2584E_5 W06 B WATER RETICULATION NOTES

ACOUSTIC FENCE

M2584E_5	AF01	D	ACOUSTIC FENCE LAYOUT PLAN - SHEET 1
M2584E_5	AF02	F	ACOUSTIC FENCE LAYOUT PLAN - SHEET 2
M2584E_5	AF03	D	ACOUSTIC FENCE 1 ELEVATION
M2584E_5	AF04	Ε	ACOUSTIC FENCE 2 ELEVATION
M2584E_5	AF05	C	ACOUSTIC FENCE SECTIONS SHEET 1
M2584E_5	AF06	C	ACOUSTIC FENCE SECTIONS SHEET 2
M2584E_5	AF07	C	ACOUSTIC FENCE SECTIONS SHEET 3
M2584E_5	AF08	C	ACOUSTIC FENCE SECTIONS SHEET 4
M2584E_5	AF09	С	ACOUSTIC FENCE SECTIONS SHEET 5

INDEX:

STAGING & SITE SURVEY PLANS

M2584E_5 L01 C CONSTRUCTION STAGING PLAN
M2584E_5 L02 B EXISTING SERVICES AND SITE SURVEY PLAN - SHEET 1 of 2

M2584E_5 L03 B EXISTING SERVICES AND SITE SURVEY PLAN - SHEET 2 of 2

EARTHWORKS PLANS

M2584E_5 EW01 E EARTHWORKS LAYOUT PLAN - SHEET 1 of 2

M2584E_5 EW03 E EARTHWORKS DETAILS LAYOUT PLAN - SHEET 1 of 4

M2584E_5 EW04 E EARTHWORKS DETAILS LAYOUT PLAN - SHEET 1 of 4

M2584E_5 EW05 H EARTHWORKS DETAILS LAYOUT PLAN - SHEET 2 of 4

M2584E_5 EW06 H EARTHWORKS DETAILS LAYOUT PLAN - SHEET 3 of 4

M2584E_5 EW06 H EARTHWORKS DETAILS LAYOUT PLAN - SHEET 4 of 4

M2584E_5 EW07 D EARTHWORKS DETAILS & NOTES PLAN SHEET 1 of 2

M2584E_5 EW08A F EARTHWORKS BIORETENTION BASIN 4 LAYOUT PLAN & DETAILS

M2584E_5 EW08B A EARTHWORKS BIORETENTION LAYOUT PLAN & DETAILS

M2584E_5 EW09 C EARTHWORKS BIORETENTION BASIN 3 LAYOUT PLAN & DETAILS

M2584E_5 EW10 B EARTHWORKS DETAILS & NOTES PLAN SHEET 2 of 2

ROADWORKS PLANS

M2584E_5R01BROADWORKS LAYOUT PLAN - SHEET 1 of 2M2584E_5R02EROADWORKS LAYOUT PLAN - SHEET 2 of 2M2584E_5R03BROADWORKS NOTES AND DETAILS PLANM2584E_5R04DROADWORKS INTERSECTION DETAILS PLAN - SHEET 1 of 2M2584E_5R05CROADWORKS INTERSECTION DETAILS PLAN - SHEET 2 of 2M2584E_5R06BROADWORKS LONGITUDINAL SECTIONS - ROAD 3 (FLINDERS STREET)M2584E_5R07BROADWORKS CROSS SECTIONS - ROAD 3 (FLINDERS STREET)-SHEET 1 OF 2M2584E_5R08BROADWORKS CROSS SECTIONS - ROAD 3 (FLINDERS STREET)-SHEET 2 OF 2M2584E_5R09AROADWORKS LONGITUDINAL SECTION - ROAD 7 (BUSHMAN COURT)M2584E_5R10BROADWORKS CROSS SECTIONS - ROAD 7 (BUSHMAN COURT)

SIGNS AND LINEMARKING PLANS

M2584E_5 SL01 C SIGNS AND LINEMARKING PLAN - SHEET 1 of 2
M2584E_5 SL02 D SIGNS AND LINEMARKING PLAN - SHEET 2 of 2

DRAINAGE PLANS

M2584E_5D01DDRAINAGE CATCHMENT PLANM2584E_5D02BDRAINAGE LAYOUT PLAN - SHEET 1 of 2M2584E_5D03EDRAINAGE LAYOUT PLAN - SHEET 2 of 2M2584E_5D04BDRAINAGE LONGITUDINAL SECTIONS LINE M, 3M, N, 1A-7M & 1B-7MM2584E_5D05CDRAINAGE LONGITUDINAL SECTIONS LINE 0, 1A-20 & JM2584E_5D06BDRAINAGE CALCULATIONS TABLE SHEET 1 of 2 - MINORM2584E_5D07BDRAINAGE CALCULATIONS TABLES SHEET 2 of 2 - MAJORM2584E_5D08ABDRAINAGE STRUCTURES DETAILS - SHEET 1 OF 2M2584E_5D09CBIORETENTION PLAN & DETAILS - SHEET 2 OF 2M2584E_5D10BBIORETENTION 9 LAN & DETAILS - BASIN 3M2584E_5D11BBIORETENTION 3 SEDIMENT FOREBAY 1 PLAN & SECTIONSM2584E_5D12DBIORETENTION PLAN & DETAILS - BASIN 4M2584E_5D13DBIORETENTION PLAN & DETAILS - BASIN 4M2584E_5D13DBIORETENTION PLAN & DETAILS - BASIN 4

EROSION & SEDIMENT CONTROL PLANS


M2584E_5ES01BEROSION AND SEDIMENT CONTROL LAYOUT - BULK EARTHWORKS PHASEM2584E_5ES02BEROSION AND SEDIMENT CONTROL LAYOUT - BULK EARTHWORKS PHASEM2584E_5ES03BEROSION AND SEDIMENT CONTROL LAYOUT - ROADS & DRAINAGE PHASEM2584E_5ES04BEROSION AND SEDIMENT CONTROL LAYOUT - ROADS & DRAINAGE PHASEM2584E_5ES05BEROSION AND SEDIMENT CONTROL LAYOUT - PRACTICAL COMPLETION PHASEM2584E_5ES06BEROSION AND SEDIMENT CONTROL LAYOUT - PRACTICAL COMPLETION PHASEM2584E_5ES07BEROSION AND SEDIMENT CONTROL DETAILS LAYOUTM2584E_5ES08BEROSION AND SEDIMENT CONTROL DETAILS SEDIMENT BASIN 1M2584E_5ES09BEROSION AND SEDIMENT CONTROL DETAILS SEDIMENT BASIN 2M2584E_5ES10AEROSION AND SEDIMENT CONTROL DETAILS SEDIMENT BASIN 2
















































ENGINEERS

MORETON BAY






CHECKED PNH A ISSUE FOR OPERATIONAL WORKS APPROVAL
DATUM: AHD ISSUE: DETAILS: 13.12.24 AM
DATE: INIT:


EARTHWORKS BIORETENTION LAYOUT PLAN & DETAILS


DFC (PROJECT MANAGEMENT PTY LTD) 'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR



M2584E_5 EW08B A







CONCRETE SLEEPER/UB POST RETAINING WALL SCALE 1:20

NOTE: RETAINING WALL DESIGN (INCLUDING FENCE POST BRACKETS AND FITTINGS) AND CONSTRUCTION CERTIFICATION TO INCORPORATE LOADING FROM FUTURE 1.8m HIGH LAPPED PALING PROPERTY FENCE



В



EARTHWORKS DETAILS & NOTES PLAN SHEET 2 OF 2

DFC (PROJECT MANAGEMENT PTY LTD)

'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR

21/10/24

M2584E_5 EW10

MORETON BAY REGIONAL COUNCIL REF: FAMILY DA/2024/2888 CORPORATION FILE NAME: EARTHWORKS, DWG

ROADWORKS NOTES

- ALL DIMENSIONS ON THE DRAWINGS ARE IN METRES UNLESS SHOWN OTHERWISE.
- ALL TURNOUT RADII ARE TO THE LIP OF THE CHANNEL
- LENGTH AND LOCATION OF MITRE DRAINS SHALL BE DETERMINED ON SITE BY THE SUPERINTENDENT
- ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH CURRENT MORETON BAY REGIONAL COUNCIL STANDARDS AND STANDARD DRAWINGS UNLESS DIRECTED OTHERWISE
- THE CONTRACTOR SHALL VERIFY LOCATIONS OF ALL EXISTING SERVICES WITH ALL RELEVANT AUTHORITIES BEFORE COMMENCING CONSTRUCTION. ANY COSTS ASSOCIATED WITH REPAIRING DAMAGE TO EXISTING SERVICES SHALL BE PAID FOR BY THE CONTRACTOR.
- THE CONTRACTOR SHALL ERECT TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE RELEVANT AUTHORITY SPECIFICATIONS
- SUB-BASE GRAVEL COMPACTED TO 95% AS1289 (MODIFIED) AND OF MINIMUM THICKNESS 75mm SHALL EXTEND UNDER THE KERB AND CHANNEL TO 150mm (MIN.) BEHIND THE KERB.
- NBN TO RECEIVE 3 WEEKS NOTICE BEFORE INSTALLATION OF CONDUITS.
- THE CONTRACTOR SHALL VERIFY OFFSET PEG LOCATIONS AND BENCH MARK LEVELS AND ADVISE THE SUPERINTENDENT OF ANY DISCREPANCY BEFORE THE COMMENCEMENT OF CONSTRUCTION.
- KERB AND CHANNEL TO BE CONSTRUCTED IN ACCORDANCE WITH MBRC STD. DWG. RS-080
- SIDE DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH MBRC STD DRAWINGS RS-140 AND 142.
 - a. TRIMMING AND COMPACTION OF SUBGRADE IS TO BE COMPLETED AND APPROVED BEFORE SUBSOIL DRAINS AND SERVICE CONDUITS ARE CONSTRUCTED. THE TRENCHES SHALL THEN BE EXCAVATED, AND THE EXCAVATED MATERIAL PLACED ON THE FOOTPATH AND NOT THE SUBGRADE
 - b. WHERE SUBSOIL DRAINS PASS UNDER SERVICE CONDUITS, THE SIDE DRAINS ARE TO BE DEEPENED AND GRADED OUT TO A NORMAL DEPTH AT A MINIMUM GRADE OF 1:250.
 - c. IN DISPERSIVE, SOLUBLE OR FINE GRAINED SOILS, THE DEVELOPER'S REPRESENTATIVE IS TO EVALUATE

GEOFABRIC WRAPPED SUBSOIL DRAINS ARE REQUIRED. WHERE GEOFABRIC WRAPPED SUBSOIL DRAINS ARE PROPOSED THE DEVELOPER'S REPRESENTATIVE IS TO PROVIDE DETAILS FOR APPROVAL BY COUNCIL'S NOMINATED REPRESENTATIVE

- d. ROAD SUBSOIL DRAINAGE MUST BE 'DAYLIGHTED' AND DISCHARGED TO AN APPROVED LEGAL POINT OF DISCHARGE. CAPS ARE TO BE PROVIDED TO UPSTREAM ENDS OF SUBSOIL DRAINS.
- EACH PAVEMENT COURSE SHOULD NOT BE COMMENCED UNTIL THE PREVIOUS COURSE HAS BEEN INSPECTED AND APPROVED AND CERTIFIED BY THE CONSULTANT WITH RESPECT TO COMPACTION, FINISHED LEVELS AND TEXTURE OF FINISH, COMPACTION TESTS OF EACH LAYER ARE REQUIRED BEFORE PROCEEDING TO THE NEXT LAYER, ALL TEST RESULTS ARE TO BE PROVIDED TO COUNCIL'S NOMINATED REPRESENTATIVE PRIOR TO SURFACING.
- SUBGRADE IS TO BE TRIMMED TO AN EVEN SURFACE FREE FROM LOOSE MATERIAL AND GRADED TO BE FREE-DRAINING. UNSUITABLE MATERIAL SUCH AS ORGANIC MATTER IS TO BE REMOVED. SUBGRADE AFFECTED BY RAINFALL AFTER FINAL TRIMMING SHALL NOT BE ACCEPTED UNTIL APPROPRIATE DRYING OUT TREATMENT HAS BFFN AFFFCTFD
- UNBOUND PAVEMENT COURSE MATERIAL IS TO BE PLACED ONLY ON UNDERLYING LAYERS MAINTAINED AT THE CORRECT MOISTURE CONTENT. PREPARED SUBGRADES AND PRECEDING LAYERS OF BASE COURSE SHALL BE MOISTENED IMMEDIATELY PRIOR TO SPREADING THE NEXT COURSE, PAVEMENT MATERIAL IS TO BE MAINTAINED AT THE SPECIFIED MOISTURE CONTENT PRIOR TO AND DURING SPREADING. THE LEADING EDGES OF THE PAVEMENT MATERIAL ARE TO BE KEPT MOIST. MINIMUM COMPACTED LAYER THICKNESS SHALL BE 100 MILLIMETRES AND MAXIMUM COMPACTED THICKNESS SHALL BE 150mm
- PRAM RAMPS TO BE CONSTRUCTED IN ACCORDANCE WITH MBRC STD DWG PC-2101A

CONCRETE PATHWAYS

CONCRETE PATHWAYS TO BE CONSTRUCTED IN ACCORDANCE WITH IPWEA STD DWG RS-065

PAVEMENT DEPTH VERIFICATION

PAVEMENT DEPTHS SHALL BE VERIFIED BY THE PROVISION OF AS CONSTRUCTED LEVELS OF THE SUBGRADE AND PRE-SEAL STAGE (OR TOP OF KERB IF INSTALLED) AT A FREQUENCY OF THREE (3) LEVELS (RIGHT HAND SIDE, CENTRE AND LEFT HAND SIDE) EVERY 50 METRES. THE SURVEYED INFORMATION IS TO BE PROVIDED IN A TABULATED FORMAT AND IS TO BE CERTIFIED BY BOTH THE SURVEYOR AND CONSULTING ENGINEER PROVIDED WITH ON MAINTENANCE SUBMISSION.

SUBGRADE TESTING

A DESIGN CALIFORNIA BEARING RATION (CBR) IS TO BE DETERMINED FOR EACH IDENTIFIABLE UNIT DEFINED ON THE BASIS OF TOPOGRAPHY, GEOLOGICAL AND DRAINAGE CONDITION OF THE SITE. THE FOUR DAY SOAKED CBR AT A COMPACTION OF 100% STANDARD COMPACTION IS TO BE THE STANDARD TEST. TESTS ARE TO BE CARRIED OUT IN A NATA REGISTERED LABORATORY (NATIONAL ASSOCIATION OF TESTING AUTHORITIES). THE SAMPLING IS TO BE RANDOMLY LOCATED WITHIN EACH LENGTH OF THE PROPOSED ROADWAY WITH CONSTANT SUBGRADE MATERIAL. IT IS REQUIRED THAT A MINIMUM OF 1 TEST PER MATERIAL TYPE BE CARRIED OUT. THE LOCATION OF MATERIAL TYPE VARIANCES ARE TO BE DETAILED IN ACCORDANCE WITH SAMPLE TEST AND ADJOINING LOT. THE SAMPLES SHALL BE TAKEN GENERALLY IN THE POSITION OF THE OUTER WHEEL PATH ON BOTH SIDES OF THE PROPOSED ROAD. A SKETCH PLAN SHOWING THE LOCATION OF ALL TESTS IS TO BE SUBMITTED WITH THE TEST RESULTS.

THE CONTRACTOR MAY BE REQUIRED. FROM TIME TO TIME, DURING THE PERIOD OF CONSTRUCTION, TO CLEAN THOSE PARTS OF THE ACCESS ROUTE TO THE SITE THAT MAY BE AFFECTED BY ANY MATERIAL DROPPED, DEPOSITED OR SPILLED ON THE ROADS AS A RESULT OF CONSTRUCTION PROCESSES ASSOCIATED WITH THE SITE, ALL CONSTRUCTION TRAFFIC TO THE SUBJECT PROPERTY SHALL BE ACCESSED VIA BRISBANE ROAD

DRIVEWAY NOTES:

ALL CONCRETE DRIVEWAYS ARE TO BE 3.0M. WIDE U.N.O., 125mm. THICK WITH F72 MESH, 50mm TOP COVER, ON A 75mm, THICK CBR15 GRAVEL BASE.

THE CONTRACTOR IS TO ENSURE THAT ALL SERVICE CONDUITS ARE IN PLACE BEFORE POURING THE

THE BACK OF KERB AND CHANNEL IS TO BE CUT DOWN AT ALL DRIVEWAY ENTRANCES

THE EXACT LOCATION AND EXTENT OF THE DRIVEWAY WILL BE DETERMINED ON SITE BY THE SUPERVISING **FNGINFFR**

COMPACTION TESTING AND FREQUENCY

DETERMINATION OF THE COMPACTION PERFORMANCE OF THE SUBGRADE AND PAVEMENT GRAVEL MATERIALS - LABORATORY REFERENCE DENSITY FIFLD DENSITY OPTIMUM MOISTURE CONTENT FIELD MOISTURE CONTENT -SHALL BE CARRIED OUT IN ACCORDANCE WITH AS1289 METHODS OF TESTING SOILS FOR ENGINEERING PURPOSES, IN PARTICULAR THE E SERIES TESTS. THE LABORATORY REFERENCE DENSITY

- NATURAL SUBGRADE 100% STANDARD MAXIMUM DRY DENSITY (MDD)
- PAVEMENT UPPER AND LOWER SUB BASE LAYERS 100% STANDARD MAXIMUM DRY DENSITY (MDD)
- PAVEMENT BASE LAYER 100% STANDARD MAXIMUM DRY DENSITY (MDD)

THE MINIMUM FREQUENCY OF TESTING SHALL BE IN ACCORDANCE WITH COUNCIL'S PLANNING SCHEME POLICY OPERATIONAL WORKS INSPECTIONS, MAINTENANCE AND BONDING PROCEDURES. PLANNING SCHEME POLICY -INTEGRATED DESIGN - PAGE 45 OF 60.

A MINIMUM OF THREE (3) TESTS PER PROJECT WILL BE REQUIRED. A SKETCH PLAN SHOWING THE LOCATION OF THE TESTS IS TO BE SUBMITTED WITH THE RESULTS. ALL TESTS ARE TO BE DISTRIBUTED REASONABLY EVENLY THROUGH THE FULL DEPTH AND AREA OF PAVEMENT.

- IN URBAN AND RURAL RESIDENTIAL AREAS, THE ASPHALTIC CONCRETE (A.C.) SURFACING THICKNESS IS
- ﴿30mm (BCC}TYPE 2) ON ACCESS TYPE STREETS AND LANEWAYS WITH TRAFFIC VOLUMES LESS THAN \triangle { 4 × 10⁵;
- 50mm (BCC TYPE 3) FOR ARTERIAL AND SUB ARTERIAL ROADS; AND
- 40mm (BCC TYPE 3) FOR ALL OTHER STREETS.

IN COMMERCIAL AND INDUSTRIAL AREAS THE MINIMUM A.C. SURFACING THICKNESS IS TO BE 40mm.

- WHERE STENCILED OR PATTERNED SURFACE TREATMENTS ARE PROPOSED AN ADDITIONAL 10mmSHALL BE ADDED TO THE DESIGN THICKNESS OF THE SURFACING. THE A.C. BINDER TYPE IS TO BE IN ACCORDANCE WITH AUSTROADS.
- A.C. SURFACINGS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH BRISBANE CITY COUNCIL STANDARDS (BCC S310 SUPPLY OF DENSE GRADED ASPHALT AND S320 LAYING OF ASPHALT).
- PRIMERS SEALS ARE REQUIRED TO BE PLACED UNDER ALL ASPHALT SURFACES. PRIMER SEALS SHALL CONSIST OF CUTBACK BITUMEN (AMC4) OR BITUMEN EMULSION TO MAIN ROADS SPECIFICATION (MRTS 11 SPRAYED BITUMINOUS SURFACINGS EXCLUDING EMULSIONS) AND MRTS 12 SPRAYED BITUMINOUS EMULSION SURFACINGS) WITH 10MM AGGREGATE. WHERE CUTBACK BITUMEN IS USED THE MINIMUM CURING TIME BEFORE THE NEXT SEALED LAYER (ASPHALT) CAN BE PLACED WILL BE FOURTEEN (14) DAYS. WHERE BITUMEN EMULSION IS USED THE MINIMUM CURING TIME BEFORE THE NEXT SEALED LAYER (ASPHALT) CAN BE PLACED WILL BE FOUR (4) DAYS.
- IN RURAL AREAS AND WHERE SPECIFIED, BITUMEN SPRAY SEAL SURFACING IS TO BE PROVIDED IN THE FORM OF A 2 COAT POLYMER SPRAY SEAL (14MM/7MM) IN ACCORDANCE WITH MAIN ROAD TECHNICAL SPECIFICATIONS (MRTS 18 POLYMER MODIFIED BINDERS, MRTS 11 SPRAYED BITUMINOUS SURFACINGS **EXCLUDING FMULSIONS).**

THE DEGREE OF SATURATION OF BASE COURSE PRIOR TO SURFACING IS TO BE LESS THAN 65%. TEST RESULTS DEMONSTRATING DEGREE OF SATURATION ARE TO BE PROVIDED TO COUNCIL'S NOMINATED REPRESENTATIVE AT THE PRESEAL INSPECTION AND AS A PART OF THE ON MAINTENANCE DOCUMENTATION.

PAVEMENT

THE ROAD PAVEMENT ADOPTED WILL BE DETERMINED BY THE ENGINEER AND APPROVED BY MORETON BAY REGIONAL COUNCIL. THIS PAVEMENT SHALL BE BASED ON SOIL TESTS TAKEN AT FORMATION LEVEL

ANY VARIATIONS TO THE NOMINAL PAVEMENT THICKNESS WILL BE PAID AT THE RATES SHOWN IN THE PRICED SCHEDULE OF RATES.

TOPSOIL

- ALL TOPSOIL ON ROADWORK AREAS SHALL BE STRIPPED AND STOCKPILED PRIOR TO THE COMMENCEMENT OF ANY ROADWORK OPERATIONS.
- A TOPSOIL DEPTH OF 150mm HAS BEEN USED TO DETERMINE TOPSOIL AND FARTHWORK QUANTITIES. THE CONTRACTOR IS TO SATISFY HIMSELF OF THE ACCURACY OF THESE QUANTITIES AND TO MAKE ANY NECESSARY ALLOWANCE IF HE DISAGREES WITH THEM.
- A TOPSOIL RESPREAD DEPTH OF 250mm ON ALLOTMENTS HAS BEEN USED TO DETERMINE EARTHWORK QUANTITIES.

IP 1 7014713.201 187°29'57.03 0.000 480858.894 TC 74.434 480849.180 7014639.404 187°29'57.03 IP 2 R = -1500023.562 90°00'00.00" 86.215 480847.222 7014624.532 СТ 97.996 7014622.574 97°29'57.03 480862.094 196.535 7014609.714 97°29′57.03 480959.789 IP 3 203.608 480966.861 7014608.783 R = -45.00014.147 18°00'45.00" СТ 210.682 480973.873 7014610.085 79°29′12.03 TC 234.589 480997.380 7014614.447 79°29′12.03 IP 4 245.192 7014616.910 R = 13.50090°00′00.00″ 481010.653 21.206 СТ 255.795 481013.116 7014603.637 169°29'12.03' 7014581514 TC 278.295 481017.222 169°29'12.03' 7014568.577 IP 5 291.345 481019.623 18°01'00.07' R = 83.00026.099 304.395 481017.904 7014555.531 CT 187°30'12.10' TC 396.875 481005.828 7014463.843 187°30′12.10″ IP 6 423.186 481001.453 7014430.629 R = 33.50052.622 90°00′00.00" CT 449.497 480968.240 7014435.004 277°30′12.10′ 641.596 480777.786 7014460.089 277°30′12.10′ IP 7 652.593 480763.903 7014461.918 R = 14.00021.994 90°00'44.90' СT 663 590 7014475.800 480765.735 7°30'57.00" Tſ 721.680 7014533.392 7°30′57.00 480773.333 IP 8 7014547.276 21.995 90°00′59.97 732.678 480775.165 R = -14.000СТ 743.676 480761.281 7014549.103 77°29′57.03 TC 863.314 480642.666 7014564.718 277°29′57.03 7014566.545 90°00′00.00″ IP 9 874.309 480628.785 R = 14.00021.991 CT 885.305 480630.613 7014580.425 7°29′57.03′ IP 10 943.305 480638.182 7014637.929 IP 11 947 459 480638 741 7014642.173 R = 14.0008.308 34°00'07.78" 951.613 IP 12 480641.577 7014645.379 IP 13 7014653.116 961.944 480648.423 41°30'02.74

ROAD 3 (BRADMAN STREET & FLINDERS STREET) CONTROL LINE DETAILS


BEARING

RAD/SPIRAL

NORTHING

CHAINAGE

EASTING



COVER ON A 75mm CBR 15 GRAVEL BASE.

THE CONTRACTOR IS TO ENSURE THAT ALL SERVICE CONDUITS ARE IN PLACE BEFORE POURING THE DRIVEWAYS.

THE BACK OF KERB AND CHANNEL IS TO BE CUT DOWN AT ALL DRIVEWAY ENTRANCES. FOR DETAILS SEE MBRC STD DWGS RS-049 & RS 050

THE SUPERVISING ENGINEER IS TO BE NOTIFIED PRIOR TO POURING CONCRETE FOR INSPECTION OF PLACED MESH

THE EXACT LOCATION AND EXTENT OF THE DRIVEWAY WILL BE DETERMINED ON SITE BY THE SUPERVISING ENGINEER EXPANSION AND CONTRACTION JOINTS TO BE CONSTRUCTED IN ACCORDANCE WITH ABOVE DETAILS





BRISBANE - SUNSHINE COAST - CENTRAL QLD PLANNERS BRISBANE House - 76 Ernest Street outh Brisbane Old 4101 P 07 3012 0100 W www.jfp.com.au

A.C.N. 050 414 045

MORETON BAY

URBAN DESIGNERS SURVEYORS ENGINEERS LANDSCAPE ARCHITECTS

THIS SCALE SHOWN IS ORIGINAL DRAWING SCALE NOT TO SCALE MINOR AMENDMENT 21/10/24 CHECKED PNH A ISSUE FOR OPERATIONAL WORKS APPROVAL

21/10/24 'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR

ROADWORKS NOTES AND DETAILS PLAN


DFC (PROJECT MANAGEMENT PTY LTD)

FAMILY


M2584E 5 В MORETON BAY REGIONAL COUNCIL REF.

DA/2024/2888 S ELLE NAME- BOADWORKS DWG

Approved Subject to Conditions of Decision Notice DA/2024/4845



INTERSECTION DETAIL - BASIN 3 DRIVEWAY No.1 SCALE 1:100



BASIN 3 DRIVEWAY SETOUT AND LEVEL TABLE

PT No.	TYPE	EASTING	NORTHING	LEVEL				
PT No. 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 45	TYPE IP IP IP IP IP IP IP IP IP	EASTING 481021.023 481025.626 481033.475 481040.871 481041.877 481044.851 481045.248 481032.256 481033.256 481031.844 481032.317 481041.851 481031.863 481032.862 481032.862 481035.838 481035.838 481035.838 481035.892 481029.682	NORTHING 7014534.792 7014534.189 7014533.368 7014532.722 7014530.014 7014524.025 7014521.014 7014522.051 7014523.632 7014533.742 7014533.742 7014536.342 7014537.766 7014480.435 7014478.300 7014484.160 7014484.160 7014483.779 7014479.630 7014479.630	LEVEL 147.581 147.764 147.299 146.824 146.122 145.357 144.466 143.921 144.466 143.921 144.466 144.296 144.697 146.296 144.508 143.933 144.508 143.933 144.508				

BASIN 4 DRIVEWAY SETOUT AND IFVFL TARLE

LLVLL TADLL							
PT No.	TYPE	EASTING	NORTHING	LEVEL			
161	IP	481158.265	7014488.881	146.320			
162	TP	481163.413	7014493.716	145.649			
163	TP	481165.032	7014494.831	145.407			
164	IP	481173.505	7014499.174	143.980			
165	IP	481174.873	7014496.505	143.982			
166	TP	481166.400	7014492.161	145.407			
167	TP	481165.467	7014491.529	145.649			
168	IP	481159.689	7014486.103	146.328			

LEGEND:

PAVEMENT CONTOURS			15.2
PROPOSED KERB AND CHANNEL	=		
PROPOSED STORMWATER		sw	
SEWERAGE		— s —	
WATER MAIN		— w ——	
LOW PRESSURE SEWERAGE MAIN	×	— LPS —	
EXISTING KERB AND CHANNEL	= = = =	= = =	= = =
EXISTING U/G ELECTRICAL		— Е —	
TELSTRA		— T ——	
THRESHOLD PAVEMENT TREATMENT			
KERB TRANSITION		•	
KERB RAMP			
TREE LEGEND		,	••••
TREES TO BE RETAINED AND PRO	TECTED		(\cdot)
TREES TO BE RETAINED AND REQU THE SUPERVISION OF ANY EXCAV OR SERVICES WORKS WITHIN THE	ATION		

PROTECTION ZONE BY AN ARBORIST ON SITE.

NOTE: ALL RADII ARE MEASURED TO THE LIP OF THE KERB AND CHANNEL. ● 1.8m LENGTH TRANSITION BETWEEN KERB TYPES UNLESS SHOWN OTHERWISE

THE CONTRACTOR IS TO NOTIFY THE SUPERVISING ENGINEER OF ANY DISCREPENCIES BETWEEN THE DESIGN PLANS AND THE CONDITIONS ON SITE PRIOR TO COMMENCEMENT OF ANY WORK.





BRISBANE - SUNSHINE COAST - CENTRAL QLD PLANNERS BRISBANE JFP House - 76 Ernest Street, SURVEYORS South Brisbane Qld 4101 ENGINEERS P 07 3012 0100 W www.jfp.com.au

A.C.N. 050 414 045

MORETON BAY

URBAN DESIGNERS LANDSCAPE ARCHITECTS



THIS SCALE SHOWN IS ORIGINAL DRAWING SCALE

A.FRASER J.PAPPAS DESIGNED CDV C BASIN 4 UPDATED
RPEQ.5691 RPEQ.6086 RAWN WN B DESIGN CHANGED TO MATCH REVISED LOT LAYOUT 13/12/24 AKM 21/10/24 FR CHECKED PNH A ISSUE FOR OPERATIONAL WORKS APPROVAL 07/09/22 CDV
DATE: INIT:

ROADWORKS INTERSECTION DETAILS PLAN -SHEET 2 OF 2


DFC (PROJECT MANAGEMENT PTY LTD)

'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR



M2584E_5

MORETON BAY REGIONAL COUNCIL REF: FAMILY DA/2024/2888 CORPORATION FILE NAME: INTERSECTIONS.DW



("LIVING RESIDENTIAL" - ACCESS STREET CH. 385.738 - CH. 705.966)






ROADWORKS LONGITUDINAL SECTIONS -ROAD 3 (FLINDERS STREET)

DFC (PROJECT MANAGEMENT PTY LTD)


'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR

M2584E_5 R06 В MORETON BAY REGIONAL COUNCIL REF: FAMILY DA/2024/2888

CORPORATION FILE NAME: ROADWORKS SECTIONS, DWG



MORETON BAY



MORETON BAY






ROADWORKS LONGITUDINAL SECTION -**ROAD 7 (BUSHMAN COURT)**

DFC (PROJECT MANAGEMENT PTY LTD)

'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR

Α MORETON BAY REGIONAL COUNCIL REF: FAMILY DA/2024/2888 CORPORATION FILE NAME: ROADWORKS SECTIONS, DWG

M2584E_5



<u>NOTES</u>

- ALL PAVEMENT MARKING AND TRAFFIC SIGNS TO BE INSTALLED IN ACCORDANCE WITH THE QUEENSLAND DEPARTMENT OF MAIN ROADS, MANUAL OF UNIFORM TRAFFIC CONTROLS DEVICES (MUTCD).
- TRAFFIC ISLAND NOSES ARE TO BE PAINTED WITH WHITE REFLECTORISED PAINT.
- RAISED REFLECTORISED PAVEMENT MARKERS (RRPM's) ARE TO BE PLACED IN ACCORDANCE WITH M.U.T.C.D. PART 2 SECTION 4653
- INSTALL TGS1 ON ALL RAMPED KERB CROSSINGS IN ACCORDANCE WITH M.B.R.C. STANDARD DRAWING PC-2170.

THE CONTRACTOR IS TO NOTIFY THE SUPERVISING ENGINEER OF ANY DISCREPENCIES BETWEEN THE DESIGN PLANS AND THE CONDITIONS ON SITE PRIOR TO COMMENCEMENT OF ANY WORK.






BRISBANE - SUNSHINE COAST - CENTRAL QLD PLANNERS BRISBANE South Brisbane Old 4101

A.C.N. 050 414 045

MORETON BAY

URBAN DESIGNERS SURVEYORS ENGINEERS LANDSCAPE ARCHITECTS





SIGNS AND LINEMARKING PLAN -SHEET 1 OF 2

DFC (PROJECT MANAGEMENT PTY LTD) 'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR


18/11/24 FR 21/10/24 FR


07/09/22 CDV
DATE: INIT:


FAMILY DA/2024/2888


M2584E_5 SL01 MORETON BAY REGIONAL COUNCIL REF:


Approved Subject to Conditions of Decision Notice DA/2024/4845














SWD Drainage Model:

Rainfall File: AUS QLD Brisbane.12dhydro

Rainfall Method IFD Table Runoff C Method: QUDM 2007 Storm Event Type: Minor

LO	OCATION			SU	B-CAT	CHMENT F	RUNOFF	=							INLET D	DESIGN										DRAII	N DESIG	iN									HEAD LO	SSES					P	ART FU	JLL				DESIGN L	LEVELS			
			Tc	1	fi	С	Α	CA	Qc Qa	a								Qg	QЬ		Tc	1	CA	Qrat	a	L	S		Vf=Q/	A Qca	p Vcap	p Vt		S/Do	Qg/Qo	Du/Do	Vf²/2g	Ku	hu	Kw	hw	Sf	hf c	dn V	√n								
DESIGN A.R.I. STRUCTURE No.		DRAINAGE SECTION	SUB-CATCHMENT TIME OF CONC.	RAINFALL INTENSITY	FRACTION IMPERVIOUS	FICIENT OF R	SUB-CATCHMENT AREA	IVALENT AREA	SUB-CATCHMENT DISCHARGE FLOW IN K&C (INC. BYPASS)	AD CAP	FLOW WIDTH	FLOW DEPTH	FLOW D x V	GRADE	ROAD XFALL AT INLET	12d INLET TYPE	12d INLET CURVE	FLOW INTO INTEL	FLOW	_S M07=	CRITICAL TIME OF CONC.	RAINFALL INTENSITY	T0TAL (C × A)	PEAK FLOW	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPE SIZE	FULL PIPE VELOCITY	CAPACITY FLOW	VEL	VEL VELOCITY	12d Ku / Kw CHART IDENTIFIERS Refer to: a) QUDM Voi. 2 Charts 32–47, b) FHWA Culvert Charts	SUBMERGENCE RATIO USED IN CHARTS	FLOW RATIO USED IN CHARTS	DIAMETER RATIO USED IN CHARTS	VELOCITY HEAD	U/S HEAD LOSS COEFFICIENT	U/S HEAD LOSS	W.S.E. COEFFICIENT	CHANGE IN W.S.E.	SLOPE	NOIL	DEPTH	NORMAL DEPTH VELOCITY	PIPE U/S I.L.	PIPE D/S I.L.	PIPE U/S H.G.L.	PIPE D/S H.G.L.	W.S.E.	GRATE LEVEL	FREEBOARD	STRUCTURE No.
years			min	mm/hr	fi	С	ha	ha L	_/s L/	's L/s	m	m	m²/s		%			L/s L	L/s				ha	L/s l	_/s	m	% г	mm	m/s	L/s	s m/s	m/s					m		m		m	%	m ı	m m	n/s r	m	m	m	m	m		m	
10 1A/20		Α	5	213	0.70	0.865 0	0.059	0.051	30 30	0				0.07	3	SAG SML E	SAG	30		LOST	5	213	0.051	30	30	8.415	0.4	375 2	0.86	111	1	2	G2	1.65	1		0.004	8.9	0.034		0.034	0.03	0.003 0.	134 0	.86 144	+.676 14	4.642	145.26	145.257	145.294 1	45.986	0.692	1A/20
2/0			5			0.865 0								0.07 3	3.11	SAG SML D		260	_	LOST													T3/T6		0.34	0.86		_		2.27	_									145.287 1			2/0
1A/3M		Α	5	_	_	0.865 0	_		_	_					3	SML D	4G,3.3X	-		5/M	5	213	0.257	152	124 1	11.073	7.01	375 2	3.56	464	4.2	2	G2	2.43			0.065	5.19		_	_	0.5	0.056 0.	133 3	.56 147	1.172 14	6.396 1	147.748		148.083	_	_	1A/3M
3/M			5		_	0.865 0								4.46 3.		SML D	4G,3.3X	-		4/M													T1/T3	3.12		1				1.45										147.742 1			3/M
1B/7M		A	5			0.865 0	0.078	0.067	40 40	0				0.06 3.	3.01	SAG SML E	SAG	40		2/N	5	213	0.067	40	40	1.618	0.82	375 2	1.2	159	1.44	2	G2	1.18	1		0.007	9.7		_	_	0.05	0.001 0.	128 1	1.2 144	,.697 14	4.684 1	145.074		145.138 1		_	1B/7M
7/M			-		0.70									+		MH 1500					_											+ -	T1/T3	1.12		0.99		_		1.71										145.095 1		_	7/M
1A/7M	-	A	- 5		0.70	0.865 0).169	0.146	87 112	2				0.06 3.	3.01	SAG SML D MH 1500		112			5	213	0.146	87	112	6.797	0.54	375 2	1.32	129	1.17	2	G2 T1/T3	1.99	1	0.99	0.052	7.07		1.71		0.31	0.024 0.	27 1.	.32 144	.754 14	4.718	145.094 1		145.465 14 145.095 1			1A/7M 7/M
1/M		Α				0.865 0	27/	0.237	1/.0 1/./	٨				5.2	2	SML D	4G,3.3X	101	39 1	1A/3M	5	213	0.237	1/.0	101 1	17.841	10.33	375 2	3.86	564	5.1	1 2	G2	1.12	1	0.99	0.043	7.67				8 77	1.621 0.	108 3	86 15	0.67 17	8 797	150.87/		151.202 1			1/M
2/M			5	_	0.70		0.177		91 91	1					3	SML D	4G,3.3X	-		_	_		_		_	61.349	_		3.13	_	_		T3/T6	1.75	0.42	1		1.78		_						_		149.083 1		149.365 1		1.862	2/M
3/M			5		0.70		_		109 125	5				4.46 3.	3.38	SML D	4G,3.3X		-	4/M												+-	T1/T3	3.12	0.24	1		-		1.45				-						147.742 1			3/M
4/M		Α	5		0.70		_		100 132						3	SML D	2G,3.3X	_	25 1	1A/7M	6.08	204	1.015	576	483 9	9.844	3.01	675 2	3.66	1459	9 4.08	2	T6/T9	1.52	0.22	0.67	0.093	2.46		2.81	_	0.33	0.032 0.:	268 3	i.66 14!	5.401 1/	÷5.105 1	146.165		146.426 14			4/M
5/M		А	5	213	0.70	0.865 0).296	0.256	151 219	9				1.75	3	SML D	2G,3.3X	146	72 !	5A/M	6.16	204	1.279	723	626 3	33.234	1.17	675 2	2.74	909	2.54	2	T9/T10	1.73	0.23	1	0.156	2.14	0.335	2.57	0.401	0.55	0.184 0	412 2	74 145	ء14 029.ذ	4.641 1	145.798	145.614	146.199 1	.46.805	0.606	5/M
5A/M		Α	5	213	0.70	0.865 0	0.027	0.024	14 86	5				1.37 3.	.02	SML E	1G,3.3X	81	5	1/N	6.44	201	1.304	729	698 1	13.514	0.15	750 2	1.58	431	1 0.98	2	T3/T6	1.4	0.11	0.9	0.127	1.85	0.236	2.16	0.275	0.39	0.053 0.	.75 1	.58 144	+.603 14	4.583 1	145.378	145.325	145.653 1	146.39	0.737	5A/M
6/M		Α			0.70											TMR MH 1500					6.55	200	1.645	915	890 1	16.741	0.4	900 2	1.99	1147	7 1.8	2	T6/T9	1.28		1	0.1	-		_	$\overline{}$	0.18	0.046 0.5	596 1	.99 144	.433 14	,4.366 1	145.104	145.074	145.356 1	46.077	0.722	6/M
7/M					0.70									$\perp \perp$		MH 1500																	T1/T3	1.12		0.99		-		1.71	-			\perp	\perp	\perp				145.095 1	_		7/M
8/M		A			0.70									$\perp \perp$		MH 1500 EX 600					6.88	198	1.868	1026	1026 2	21.582	0.4 1	1050 2	2.74	2505	5 2.89	2	T10	1.18		1	0.072	2.09	0.15	2.66	0.19	0.88	0.037 0.4	+69 2	.74 144	226 1/	44.14 1	144.798		144.989 1		1.28	8/M
9/M			_		0.70		-+		_					+		HW															_	_								-		-		+	+	+	\dashv	\longrightarrow	.——!	144.609 1	145.19	\longrightarrow	9/M
1/N		A	5		0.70		_		164 169	9				0.07	3	SAG SML E	SAG	169		LOST					169			900x 450 RCB0		557			G2	1.9	1		0.009		0.067	-	_					_				145.43			1/N
2/N		A	5			0.865 0	0.059	0.051	30 30	0				0.24 2.	1.99	SAG SML E	SAG	30								17.862	_	900x 450 RCB0		556			T9/T10	1.87	0.15	1	0.012			2.52										145.365 1			2/N
6/M		A			0.70									\vdash		TMR MH 1500		$\perp \perp$			_			915	_		_	900 2	1.99		7 1.8		T6/T9	1.28		1	0.1	_	_	_	_	_		_		_	_			145.356 1	_	_	6/M
1/0		A	5		-	0.865 0				1						RW 600x600 GRATE		11			5	213	0.019	481	481	10.79	0.4	600 2	1.7	388	1.37	2	T6/T9	1.93	0.01	1	0.148	_	_	_	_	0.61	0.066 0	.6 1	1.7 144	.527 14	4.484 1	145.323		145.683 1			1/0
2/0			5	213	+	0.865 0	0.717	0.62	367 36	i I				0.07 3	3.11	SAG SML D	SAG	260	107									1500				1	T3/T6	1.29	0.34	0.86		1.99	0.211	2.27	0.241	_		+	+	-	-+	\rightarrow		145.287 1			2/0
2A/0		A			0.70									\vdash		MH 1500 EX 900					_		0.692		766 2			1500 RCB0					T1	1		0.89	0.066							_	_	_				144.623 1			2A/0
3/0		Α			0.70									$\perp \perp \perp$		CUSTOM MANHOLE					5.56	208	0.692	870	764	5.1	0.4 x	1500 K450 RCB0	1.73	1020	0 1.51	2	T10	1.39		1	0.065	2.09	0.136	2.66	0.174	0.46	0.02 0.3	£95 1.1	.73 147	4.19 1/	+4.17 1/	.44.488 1		144.662 1		0.693	3/0
4/0			1		0.70									$\perp \perp$		HW		$\perp \perp$																\perp										\perp	\perp	\perp	\perp			144.465 1	144.77	\rightarrow	4/0
1/5			1											++																														\rightarrow	\perp			\rightarrow				\rightarrow	
2/5			_											++																				+										-	+	-	$-\!\!\!\!+$					\rightarrow	
1/0														طلب																														\bot			$-\!\!\perp$	\longrightarrow	\longrightarrow		$-\!\!-\!\!\!\perp$	$-\!\!\perp$	






BRISBANE - SUNSHINE COAST - CENTRAL QLD PLANNERS BRISBANE JFP House - 76 Ernest Street, South Brisbane Qld 4101 P 07 3012 0100 W www.jfp.com.au

MORETON BAY





DRAINAGE CALCULATIONS TABLE SHEET 1 OF 2 - MINOR

DENNIS
FAMILY
CORPORATION
FILE NAME: DRAINAGE SECTIONS.DWG

M2584E_5 D06 В

DFC (PROJECT MANAGEMENT PTY LTD)

SWD Drainage Model:

Rainfall File: AUS QLD Brisbane.12dhydro

Rainfall Method IFD Table Runoff C Method: QUDM 2007 Storm Event Type: Minor

LO	OCATION			SUB-0	ATCHM	ENT RUI	NOFF									INLET [DESIGN										DRA	IN DES	IGN										HEAD	LOSSES	S					PA	ART FU	/LL				DESIGN	LEVELS			
			Tc	1 1	fi C	А	, C	A 0	ac Qa	а									Qg	QЬ		Tc	1	CA	Qrat	Q	L	S		۷f	=Q/A	Qcap	Vcap	Vt		S/Do	Qg/Qo	Du/Do	Vf ² /2	2g Kı	J hu	u K	w hv	v S	f h	f dı	In V	/n								
DESIGN A.R.I. STRUCTURE No.		DRAINAGE SECTION	SUB-CATCHMENT TIME OF CONC.	ALL IN	FRACTION IMPERVIOUS COEFFICIENT OF RUNOFF C= Aix Gi+ Ap x Cp	1 6	֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓	EUUIVALENI AKEA	SUB-LATCHMENT DISCHARGE FLOW IN K&C (INC. BYPASS)	AD CAPACITY	_		DEP	> ×	GRADE AT	KUAU XFALL AI INLEI	12d INLET TYPE	12d INLET CURVE	FLOW INTO INTEL	BYPASS FLOW	BYPASS FLOW STRUCTURE	CRITICAL TIME OF CONC.	RAINFALL INTENSITY	T0TAL (C × A)	PEAK FLOW	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPE SIZE	LLASS	FULL PIPE VELOCITY	CAPACITY FLOW	CAPACITY VELOCITY	VEL VELOCITY	to: a) QUDM Vol. 2 Charts 32-47, b) FHWA Culvert Charts	SUBMERGENCE RATIO USED IN CHARTS	FLOW RATIO USED IN CHARTS	DIAMETER RATIO USED IN CHARTS	VELOCITY HEAD	U/S HEAD LOSS COEFFICIENT		W. S. F. COEFECTION T	A NG	: F			DEPTH	NORMAL DEPTH VELOCITY	PIPE U/S I.L.	PIPE D/S I.L.	PIPE U/S H.G.L.	PIPE D/S H.G.L.	W.S.E.	GRATE LEVEL	FREEBOARD	STRUCTURE No.
years			min mm			ha	a h	ia L	/s L/:		_			² /s		%				L/s			mm/hr	_	L/s	L/s			mm	п	n/s	L/s	m/s i						m		m	1	m		6 г) П	n m	ı/s	m	m	m	m	m	m	m	
50 1A/20		А	5 28	88 0.	70 0.96	4 0.05									0.07	3	SAG SML E	SAG	40	5	LOST	5	288	0.057	46	40	8.415	0.4	375	2 (0.92	111	1	2	G2	1.43	1		0.007	9.7	7 0.06	66	0.06	56 0.0	5 0.0	04 0.19	156 0	.92 14	4.676 1	144.642	145.146	145.142	145.212	145.986	0.774	1A/20
2/0			5 28	88 0	.7 0.96	4 0.71	17 0.6	592 5	53 553	3					0.07 3	.11	SAG SML D	SAG	130	423	LOST														T3/T6	1.21	0.2	0.86		2.0	5 0.15	58 2.2	8 0.17	75									145.159	145.985	0.826	2/0
1A/3M		A	5 28	88 0	.7 0.96	4 0.29	98 0.2	287 2	30 336	6					5.2	3	SML D	4G,3.3X	140	196	5/M	5	288	0.287	230	140	11.073	7.01	375	2	3.68	464	4.2	2	G2	3.19	1		0.082	3.6	0.29	93	0.29	93 0.6	3 0.	0.1	141 3	.68 14	7.172 1	146.396	148.074	148.004	148.368	148.4	0.033	1A/3M
3/M			5 28	88 0	.7 0.96	4 0.21	13 0.2	205 16	64 22	:1					4.46 3.	38	SML D	4G,3.3X	68	153	4/M														T3	3.81	0.17	1		1.15	5 0.33	37 1.3	3 0.38	39									148.056	148.066	0.01	3/M
1B/7M		Α	5 28	_	.7 0.96	4 0.07	78 0.0)75 6	60)					0.06 3.	.01	SAG SML E	SAG	24	36	2/N	5	288	0.075	60	24	1.618	0.82	375	2	1.03	159	1.44	2	G2	1.75	1		0.002	8.3	_	_		19 0.0	12	0.0	.97 1	.03 14	4.697 1	44.684	145.333	145.333				1B/7M
7/M					.7												MH 1500																		T3/T6	1.23		0.99			_		6 0.24	_								$\perp \perp \downarrow$			0.748	
1A/7M		Α	5 28	_	.7 0.96	4 0.16	59 0.1	163 1:	31 293	3					0.06 3.	.01	SAG SML D		293			5	288	0.163	131	293	6.797	0.54	375	2 :	2.65	129	1.17	2	G2	3.54	1		0.201	3.2	_	_	_	_	6 0.1	06 0.3	.75 2	.65 14/	4.754 1	144.718	145.439	145.333				1A/7M
7/M					.7												MH 1500																		T3/T6	1.23		0.99		_	_	_	6 0.24	_			\perp	_	_			igspace			0.748	7/M
1/M		A		_	.7 0.96	_	_		_		-	+		_	5.2	3	SML D	4G,3.3X	_	-	1A/3M	5		_	_	_	17.841		_	_		564	5.1	2	G2	1.92	1	-		7.4	_	_	_	_	_	_	_	_	_			149.341				1/M
2/M		A		_	.7 0.96	_	_	_	37 137	_	_	_			5.2		SML D	4G,3.3X	_	57	3/M	5.15	286	0.436	347	183	61.349	3.85	375	2	3.17	344	3.12	2	T3/T6	1.82	0.43		0.141		_	_	8 0.30	_	7 1.1	22 0.19	95 3	.17 143	8.777 1	.46.415	149.09	148.004				2/M 3/M
3/M 4/M		A			.7 0.96	_	_		_	_	+	+		_	4.46 3. 1.75		SML D SML D	4G,3.3X 2G,3.3X	_	-	4/M 1A/7M	6.08	275	1122	944	ENO	9.844	2.01	675	2	3.71	1/ 50	4.08	2	T3 T6/T9	3.81 2.11	0.17		0.103	_	_	_	3 0.38	_	24 0.0	24 0.2	275 2	71 1/	E / 01	1/ 5 105	1/4 50	146.544		148.066		3/M 4/M
5/M		A		-	.7 0.96	_	_		28 424	_	+-	+		_	1.75	_	SML D	2G,3.3X	_	-	5A/M	6.16	274	1.427	_		33.234		675	_		909	_	_	T9/T10	2.33	0.25	1	0.103	_	_	_	_	_	_	_	_	_		_		145.999	_		_	5/M
5A/M				_	.7 0.96	_	_		-	_	+	+		_	1.37 3.	_	SML E	1G,3.3X	_			6.44	271	_	_	_			750	_		_	0.98	_	T3/T6	1.91	0.17	0.9	0.164	_	_	_	_	_	_		_	_		_		145.649				5A/M
6/M		Α	1	0	_	1				-						-	TMR MH 1500	,	1,51	+		6.55	270	_	_	-			900	_		-				1.39	****	1	0.122			_			_	_	_			_		145.333				6/M
7/M				0	_							\top					MH 1500		\vdash			1												-		1.23		0.99	1	_		-	6 0.24	_				-							0.748	
8/M		Α		0	.7												MH 1500 EX 600					6.88	266	2.085	1539	1272	21.582	0.4	1050	2 :	2.89	2505	2.89	2	T10	1.28		1	0.11	2.0	9 0.2	23 2.6	6 0.29	93 0.9	91 0.0	38 0.5	i31 2	89 14	4.226	144.14	144.867	144.671	145.16	146.269	1.11	8/M
9/M				0	.7												HW																																				144.671	145.19		9/M
1/N		Α	5 28	88 0	.7 0.96	4 0.3	2 0.3	309 24	47 387	7					0.07	3	SAG SML E	SAG	120	267	LOST	5	288	0.309	247	120	8.235		900× 450 R0		1.04	557	1.37	2	G2	2.5	1		0.004	4.8	9 0.02	22	0.02	22 0.0	0.0	02 0.1	.28 1.	.04 14	4.577 1	44.544	145.682	145.68	145.704	145.707	0.003	1/N
2/N		Α	5 28	88 0	.7 0.96	4 0.05	59 0.0	57 4	6 82	2					0.24 2.	99	SAG SML E	SAG	82		LOST	5.07	287	0.366	292	201	17.862	0.4	900x 450 R0	ВС	1.24	556	1.37	2 1	T9/T10	2.58	0.41	1	0.013	1.70	6 0.02	22 2.0	0.02	25 0.0	0.0	09 0.1	.18 1.:	1.24 144	4.524 1	.44.453	145.658	145.649	145.683	145.707	0.023	2/N
6/M		A	\vdash	0	.7												TMR MH 1500					6.55	270	1.835	1375	982	16.741		900	_	2.02	1147	1.8	2	T6/T9	1.39		1	0.122	2.2	2 0.26	67 2.	5 0.30	0.2	9 0.0	49 0.6	41 2	.02 14	4.433 1	144.366	145.382	145.333	145.686	146.077	0.391	6/M
1/0		A	5 28	88 0	.7 0.96	4 0.02	22 0.0	021 1	17 17			╧			-2	2.5 F	RW 600x600 GRATE		17			5	288	0.021	487	487	10.79	0.4	600	2	1.72	388	1.37	2	T6/T9	1.77	0.02	1	0.151	2.1	7 0.32	28 2.5	3 0.38	32 0.6	3 0.0	68 0.	.6 1	.72 14	4.527 1	.44.484	145.21	145.142	145.592	146.314	0.722	1/0
2/0			5 28	88 0	.7 0.96	4 0.71	17 0.6	592 5	53 553	3					0.07 3	.11	SAG SML D	SAG	130	423	LOST														T3/T6	1.21	0.2	0.86		2.0	5 0.19	58 2.2	8 0.17	75			\bot						145.159	145.985	0.826	2/0
2A/0		Α		0	.7												MH 1500 EX 900					5.39	283	0.771	1077	649	20.018		1500 RC ×450 RC		1.64	1021	1.51	2	T1	1		0.89	0.047					0.0	0.0	57 0.2	64 1.	.64 14	.4.291	144.21	144.558	144.554	144.558	146.167	1.609	2A/0
3/0		Α		0	.7												CUSTOM MANHOLE					5.56	281	0.771	1073	644	5.1	0.4	1500 R0	ВС	1.63	1020	1.51	2	T10	1.27		1	0.046	2.0	9 0.09	97 2.6	6 0.12	24 0.4	6 0.	0.2	.63 1	.63 14	+4.19	144.17	144.456	144.433	144.58	145.355	0.775	3/0
4/0				0	.7												HW																																				144.433	144.77		4/0
1/S																																																								
2/S																																																_				lacksquare			\perp	
1/0																			1																																	1	, !	(1 '	1


REFER M2584E 5 D08 FOR ALLOWABLE STORMWATER PIPE CONSTRUCTION EQUIPMENT LOAD TABLE





BRISBANE - SUNSHINE COAST - CENTRAL QLD PLANNERS URBAN DESIGNERS SURVEYORS ENGINEERS LANDSCAPE ARCHITECTS

MORETON BAY



DRAINAGE CALCULATIONS TABLES SHEET 2 OF 2 - MAJOR

DFC (PROJECT MANAGEMENT PTY LTD)



M2584E_5 D07 В


CONSTRUCTION	PIPE			MINIMU	IM COMPAC	TION COVEF	TO PIPE OI	BVERT		
EQUIPMENT	CLASS	Ø375	Ø450	ø525	Ø600	Ø675	Ø750	Ø825	Ø900	Ø1050
VIBRATORY RAMMER	2	0.450	0.400	0.400	0.350	0.350	0.300	0.300	0.250	0.25
(UP TO 75kg)	3	0.300	0.300	0.300	0.250	0.250	0.200	0.200	0.200	0.200
VIBRATORY TRENCH	2	0.400	0.400	0.350	0.250	0.250	0.200	0.200	0.200	0.200
ROLLER (UP TO 2t)	3	0.250	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
VIBRATORY SMOOTH	2	0.700	0.700	0.650	0.650	0.650	0.600	0.600	0.400	0.400
DRUM ROLLER (7†)	3	0.450	0.450	0.450	0.350	0.350	0.200	0.200	0.200	0.200
VIBRATORY SMOOTH	2	0.850	0.850	0.800	0.800	0.800	0.750	0.750	0.750	0.750
DRUM ROLLER (10+)	3	0.550	0.550	0.500	0.500	0.500	0.200	0.200	0.200	0.200
EXCAVATOR AND	2	0.700	0.650	0.650	0.650	0.650	0.600	0.600	0.550	0.550
COMPACTION WHEEL (15+)	3	0.450	0.450	0.450	0.450	0.450	0.350	0.350	0.250	0.250
EXCAVATOR AND	2	1.050	1.000	0.950	0.900	0.900	0.850	0.850	0.750	0.750
COMPACTION WHEEL (25t)	3	0.650	0.650	0.650	0.650	0.650	0.600	0.600	0.500	0.500
GRADER [CAT120H]	2	0.600	0.600	0.450	0.200	0.200	0.200	0.200	0.200	0.200
14.5†)	3	0.600	0.450	0.450	0.200	0.200	0.200	0.200	0.200	0.200
GRADER [CAT140H]	2	0.600	0.600	0.600	0.200	0.200	0.200	0.200	0.200	0.200
(17.0†)	3	0.600	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
SCRAPER [CAT613C11]	2	0.600	0.600	0.600	0.600	0.600	0.600	0.600	0.200	0.200
(27.2†)	3	0.600	0.600	0.600	0.600	0.600	0.200	0.200	0.200	0.200
SCRAPER [CAT621F]	2	0.700	0.650	0.650	0.650	0.600	0.600	0.600	0.600	0.600
(53.8†)	3	0.650	0.600	0.600	0.650	0.600	0.600	0.600	0.600	0.600
DOZED [CATDZ C]	2	0.600	0.600	0.600	0.200	0.200	0.200	0.200	0.200	0.200
DOZER [CATD7 G]	3	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
D07ED [CATD0 D]	2	0.600	0.600	0.600	0.600	0.600	0.600	0.600	0.600	0.200
DOZER [CATD9 R]	3	0.600	0.600	0.600	0.600	0.600	0.200	0.200	0.200	0.200
EXCAVATOR [CAT315B]	2	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
(15.8†)	3	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
EXCAVATOR [CAT317]	2	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
(17.3t)	3	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
EXCAVATOR [CAT325B]	2	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200
(25.9t)	3	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200	0.200

NOTES:

- SOIL TYPE USED FOR THIS TABLE IS CLAYEY SAND. ALL OTHER SOIL TYPES MUST BE REFERRED IMMEDIATELY TO THE SUPERVISING ENGINEER SO MINIMUM COVERS CAN BE CALCULATED.
- 2. INSTALLATION TYPE FOR THIS TABLE IS HS2. (REFER DETAIL)
- ANY CONSTRUCTION EQUIPMENT, INSTALLATION TYPE, PIPE CLASS OR PIPE DIAMETER NOT COVERED IN THIS TABLE SHOULD BE REFERRED ONTO THE SUPERVISING ENGINEER BEFORE ANY CONSTRUCTION COMMENCES
- DISTANCES SHOWN ARE THE ABSOLUTE MINIMUM COMPACTION COVER TO THE OBVERT OF THE STORMWATER PIPE FOR THE NOMINATED MACHINERY. THE CONTRACTOR IS TO ENSURE THAT MACHINES THAT REQUIRE HIGHER COMPACTION COVER ARE KEPT CLEAR OF STORMWATER PIPES AND TRENCHES UNTIL THEIR NECESSARY COMPACTION COVER IS ACHIEVED.
- CONSTRUCTION EQUIPMENT LISTED IN THIS TABLE ARE EXAMPLES ONLY AND EQUIVALENT MACHINERY MAY BE USED.

NOTE: CRACKED PIPES WILL NOT BE ACCEPTED AT 'ON MAINTENANCE' AND IT IS TO BE DEMONSTRATED IN ACCORDANCE WITH COUNCIL STANDARDS THAT THE STORMWATER SYSTEM IS ACCEPTABLE TO COUNCIL WITH REGARD TO CRACKED PIPES. (THE CONTRACTOR IS TO REFER TO SECTION 6.5.1 OF THE SUBDIVISION AND DEVELOPMENT GUIDELINES FOR FURTHER INFORMATION.)

STORMWATER PIPE BEDDING TO BE IN ACCORDANCE WITH IPWEA STANDARD DRAWING DS-030



21/10/24

07/09/22 CDV DATE: INIT:









ENGINEERS

MORETON BAY








DFC (PROJECT MANAGEMENT PTY LTD) 'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR

D08A

MORETON BAY REGIONAL COUNCIL REF: FAMILY DA/2024/2888 CORPORATION FILE NAME: DRAINAGE STRUCTURES, DWG

В


DRAINAGE STRUCTURE TO DESIGNED AND CERTIFIED BY A STRUCTURAL REGISTERED PROFESSIONAL ENGINEER(RPEQ) AND APPROVED BY THE RELEVANT AUTHORITY PRIOR TO CONSTRUCTION WORKS BEING UNDERTAKEN




STRUCTURE 3/0 CUSTOM STRUCTURE

SCALE 1:20

MORETON BAY



STRUCTURE 3/0 - SECTION A-A
CUSTOM STRUCTURE
SCALE 1: 20






TY LTD)

DENN
FAMIL





UNDER-DRAIN CLEANOUT TYPICAL DETAIL (REFER TO MBRC STD DWG MBRC-2108)

Ø100 MIN. SLOTTED RIGID PIPE (HDPE) OR APPROVED

EQUIVALENT 1 in 200 MINIMUM GRADE AT MAXIMUM

BIORETENTION 3 UNDER-DRAIN SIZING DESIGN CRITERIA

-ø600 RCP

U/S IL 142.600

LD/S IL 142.579

GRADE 0.75%

ING - 2.75m

U/S IL 142.646

-D/S IL 142.620

LNG - 3.46m GRADE 0.75%

FIFLD INLET

MANHOLE NO

CONCRETE

SURROUND

GRATE ON 1350 Ø

PIPE REACH		BIORETEN	ITION PRO	PERTIES			INDER-DR	AIN PIP	E SIZING	
	'K _{SAT} ' INFILTRATION RATE (mm/hr)	'A' BIORETENTION FILTER AREA (m²)	'h' EXTENDED DETENTION DEPTH (m)	'd' BIORETENTION FILTER DEPTH (m)	'Q _{max} ' FLOW THROUGH FILTER (l/s)	Q _{SLOTTED} REQUIRED PIPE FLOW (L/s)	PIPE DIAMETER (mm)	PIPE GRADE (%)	PIPE CAPACITY (SINGLE) (I/s)	NUMBER OF PIPES
UNDER-DRAIN SLOTTED BRANCH PIPE	180	803	0.30	0.50	64.2	77.1	100	1.0	6.1	13
UNDER-DRAIN COLLECTOR PIPE	180	803	0.30	0.50	64.2	77.1	300	0.5	80.8	1

BASIN TO BE LEFT IN PROTECTED STATE FOR 24MONTHS (MAINTENANCE PERIOD) TO ALLOW SUBSTANTIAL AMOUNT OF BUILDING WORK TO BE COMPLETED.

PROVIDE ENDICAP

AT HEAD OF PIPE

- PRIOR TO PLANTING, THE PROTECTIVE LAYER IS REMOVED AND A MINIMUM OF THREE (3) IN-SITU INFILTRATION TESTS ARE PROVIDED THAT DEMONSTRATE THAT THE HYDRAULIC CONDUCTIVITY MEETS OR EXCEEDS THE DESIGN HYDRAULIC CONDUCTIVITY (TYPICALLY 180mm/h). THIS IS TO BE NOTED ON PLANS. AVERAGE: VALUES ARE NOT ACCEPTABLE
- UPON SUCCESSFUL INFILTRATION TESTS AND PRIOR TO OFF MAINTENANCE THE BASIN IS TO BE PLANTED OUT AND A FURTHER 12 MONTH MAINTENANCE SECURITY TAKEN FOR LANDSCAPING

PROPOSED STORMWATER DRAINAGE

PROPOSED UNDER DRAINAGE Ø100 SLOTTED PIPE

PROPOSED UNDER DRAINAGE Ø225 NON SLOTTED PIPE

PROPOSED UNDER DRAINAGE Ø300 NON SLOTTED PIPE

STRUCTURE NUMBERS



FENCE (REFER LANDSCAPE

BIORETENTION MEDIA SPECIFICATION

FILTER MATERIAL SHELL BE GRADED AND CAN BE SILICEOUS OR CALCAREOUS IN ORIGIN. THE FILTER MATERIAL SHALL BE EVENLY PLACED AND LIGHTLY COMPACTED. THE FILTER MATERIAL SHALL COMPLY WITH THE FOLLOWING

SANDY LOAM OR APPROVED EQUIVALENT WITH A HYDRAULIC CONDUCTIVITY OF 180mm/hr AND BE FREE FROM RUBBISH AND DETRITUS MATERIAL.

PARTICLE SIZE:

TYPICAL SOIL COMPOSITION WOULD BE: CLAY 5-15% (PARTICLE SIZE <0.002mm) SILT <30% (PARTICLE SIZE 0.002-0.05mm) SAND 50%-70% (PARTICLE SIZE 0.05mm-2.0mm) AND APPROVED MATERIAL DOES NOT HAVE TO BE SCREENED TO REMOVE LARGE PARTICLES.

ORGANIC CONTENT: ACCEPTABLE RANGE BETWEEN 5%-10%, MEASURED IN ACCORDANCE WITH AS1289 4.1.1

6.0 TO 7.5, SILICEOUS MATERIAL MAY BE LOWER.

TRANSITIONAL LAYER

SHALL BE WELL GRADED SAND OR COURSE SAND MATERIAL. THE GRADING OF THE TRANSITIONAL LAYER SHALL COMPLY WITH THE FOLLOWING CRITERIA:

% PASSING 14mm 100%

1.0mm 80% 0.7mm 44%

0.5mm 8.4% THE TRANSITIONAL LAYER SHALL HAVE A HYDRAULIC CONDUCTIVITY OF 1800mm/hr

DRAINAGE LAYER:

SHALL BE WELL GRADED COURSE SAND OR SCREENINGS (2mm OR 5mm) AND SHALL HAVE A MINIMUM HYDRAULIC CONDUCTIVITY OF 3600mm/hr.





BRISBANE - SUNSHINE COAST - CENTRAL QLD BRISBANE House - 76 Ernest Street outh Brisbane Old 4101 P 07 3012 0100 W www.jfp.com.au

C.N. 050 414 045

MORETON BAY

EXISTING SERVICES LOCATIONS

THE DESIGN DETAILED ON THIS PLAN HAS BEEN PREPARED BASED

ON SERVICE AUTHORITY AS CONSTRUCTED INFORMATION.

NO POT HOLING HAS BEEN UNDERTAKEN TO VERIFY EXISTING

SERVICES LOCATIONS AND DEPTHS.

IT IS THE CONTRACTORS RESPONSIBILITY TO UNDERTAKE POT HOLING

(HYDROVAC EXCAVATION) PRIOR TO COMMENCEMENT OF CONSTRUCTION.

ENGINEER OF ANY DISCREPENCIES BETWEEN THE DESIGN

PRIOR TO COMMENCEMENT OF WORKS

REFER TO VEGETATION MANAGEMENT

PLAN. REHABILITATION PLAN AND

LANDSCAPE ARCHITECTS PLANS

THE CONTRACTOR IS TO NOTIFY THE SUPERVISING

PLANS AND THE CONDITIONS ON SITE PRIOR TO COMMENCEMENT OF ANY PIPE LAYING.

> URBAN DESIGNERS SURVEYORS ENGINEERS LANDSCAPE ARCHITECTS



144.05

*1 E481058.508

N7014496.24

GRATE LEVEL

PIT LIP LEVEL 144.05

RI 144,225

TYPF 1

OUTLET DETAIL



BASIN 3 PIT UPDATED 13/12/24 SCOUR PROTECTION ON WEIR, SW HEADWALLS & OUTLET PIPE LENGTH | 29/10/24 | FR ISSUE FOR OPERATIONAL WORKS APPROVAL 07/09/22 CDV DATE: INIT:

BIORETENTION PLAN & DETAILS - BASIN 3

DFC (PROJECT MANAGEMENT PTY LTD)


'ARCHERS WAY' ESTATE - STAGE 5 AT 22-80 CASH STREET, D'AGUILAR





M2584E 5 D09 \mathbf{C} MORETON BAY REGIONAL COUNCIL REF. DA/2024/2888


FILE NAME: BIORETENTION.DWG


Approved Subject to Conditions of Decision Notice DA/2024/4845





















AT 22-80 CASH STREET, D'AGUILAR

CORPORATION FILE NAME: ROADWORKS SECTIONS, DWG

A.C.N. 050 414 045

MORETON BAY



ATTACHMENT 4

Appeal Rights

Chapter 6 Dispute resolution

Part 1 Appeal rights

229 Appeals to tribunal or P&E Court

- (1) Schedule 1 states—
 - (a) matters that may be appealed to—
 - (i) either a tribunal or the P&E Court; or
 - (ii) only a tribunal; or
 - (iii) only the P&E Court; and
 - (b) the person—
 - (i) who may appeal a matter (the *appellant*); and
 - (ii) who is a respondent in an appeal of the matter; and
 - (iii) who is a co-respondent in an appeal of the matter; and
 - (iv) who may elect to be a co-respondent in an appeal of the matter.
- (2) An appellant may start an appeal within the appeal period.
- (3) The appeal period is—
 - (a) for an appeal by a building advisory agency—10 business days after a decision notice for the decision is given to the agency; or
 - (b) for an appeal against a deemed refusal—at any time after the deemed refusal happens; or
 - (c) for an appeal against a decision of the Minister, under chapter 7, part 4, to register premises or to renew the registration of premises—20 business days after a notice is published under section 269(3)(a) or (4); or

- (d) for an appeal against an infrastructure charges notice—20 business days after the infrastructure charges notice is given to the person; or
- (e) for an appeal about a deemed approval of a development application for which a decision notice has not been given—30 business days after the applicant gives the deemed approval notice to the assessment manager; or
- (f) for an appeal relating to the *Plumbing and Drainage Act* 2018—
 - (i) for an appeal against an enforcement notice given because of a belief mentioned in the *Plumbing and Drainage Act 2018*, section 143(2)(a)(i), (b) or (c)—5 business days after the day the notice is given; or
 - (ii) for an appeal against a decision of a local government or an inspector to give an action notice under the *Plumbing and Drainage Act 2018*—5 business days after the notice is given; or
 - (iii) for an appeal against a failure to make a decision about an application or other matter under the Plumbing and Drainage Act 2018—at anytime after the period within which the application or matter was required to be decided ends; or
 - (iv) otherwise—20 business days after the day the notice is given; or
- (g) for any other appeal—20 business days after a notice of the decision for the matter, including an enforcement notice, is given to the person.

Note-

See the P&E Court Act for the court's power to extend the appeal period.

(4) Each respondent and co-respondent for an appeal may be heard in the appeal.

- (5) If an appeal is only about a referral agency's response, the assessment manager may apply to the tribunal or P&E Court to withdraw from the appeal.
- (6) To remove any doubt, it is declared that an appeal against an infrastructure charges notice must not be about—
 - (a) the adopted charge itself; or
 - (b) for a decision about an offset or refund—
 - the establishment cost of trunk infrastructure identified in a LGIP; or
 - the cost of infrastructure decided using the method included in the local government's charges resolution.

230 Notice of appeal

- (1) An appellant starts an appeal by lodging, with the registrar of the tribunal or P&E Court, a notice of appeal that—
 - (a) is in the approved form; and
 - (b) succinctly states the grounds of the appeal.
- (2) The notice of appeal must be accompanied by the required fee.
- (3) The appellant or, for an appeal to a tribunal, the registrar, must, within the service period, give a copy of the notice of appeal to—
 - (a) the respondent for the appeal; and
 - (b) each co-respondent for the appeal; and
 - (c) for an appeal about a development application under schedule 1, section 1, table 1, item 1—each principal submitter for the application whose submission has not been withdrawn; and
 - (d) for an appeal about a change application under schedule 1, section 1, table 1, item 2—each principal submitter for the application whose submission has not been withdrawn; and

- (e) each person who may elect to be a co-respondent for the appeal other than an eligible submitter for a development application or change application the subject of the appeal; and
- (f) for an appeal to the P&E Court—the chief executive;
 and
- (g) for an appeal to a tribunal under another Act—any other person who the registrar considers appropriate.

(4) The service period is-

- if a submitter or advice agency started the appeal in the P&E Court—2 business days after the appeal is started; or
- (b) otherwise—10 business days after the appeal is started.
- (5) A notice of appeal given to a person who may elect to be a co-respondent must state the effect of subsection (6).
- (6) A person elects to be a co-respondent to an appeal by filing a notice of election in the approved form—
 - (a) if a copy of the notice of appeal is given to the person—within 10 business days after the copy is given to the person; or
 - (b) otherwise—within 15 business days after the notice of appeal is lodged with the registrar of the tribunal or the P&E Court.
- (7) Despite any other Act or rules of court to the contrary, a copy of a notice of appeal may be given to the chief executive by emailing the copy to the chief executive at the email address stated on the department's website for this purpose.

231 Non-appealable decisions and matters

(1) Subject to this chapter, section 316(2), schedule 1 and the P&E Court Act, unless the Supreme Court decides a decision or other matter under this Act is affected by jurisdictional error, the decision or matter is non-appealable.

- (2) The Judicial Review Act 1991, part 5 applies to the decision or matter to the extent it is affected by jurisdictional error.
- (3) A person who, but for subsection (1) could have made an application under the *Judicial Review Act 1991* in relation to the decision or matter, may apply under part 4 of that Act for a statement of reasons in relation to the decision or matter.
- (4) In this section—

decision includes-

- (a) conduct engaged in for the purpose of making a decision; and
- (b) other conduct that relates to the making of a decision;
 and
- (c) the making of a decision or the failure to make a decision; and
- (d) a purported decision; and
- (e) a deemed refusal.

non-appealable, for a decision or matter, means the decision or matter—

- (a) is final and conclusive; and
- (b) may not be challenged, appealed against, reviewed, quashed, set aside or called into question in any other way under the *Judicial Review Act 1991* or otherwise, whether by the Supreme Court, another court, any tribunal or another entity; and
- (c) is not subject to any declaratory, injunctive or other order of the Supreme Court, another court, any tribunal or another entity on any ground.

232 Rules of the P&E Court

- (1) A person who is appealing to the P&E Court must comply with the rules of the court that apply to the appeal.
- (2) However, the P&E Court may hear and decide an appeal even if the person has not complied with rules of the P&E Court.