



File Name:-P.0551355.D.02N.xls			NBN CO. CIVIL CONDUIT SCHEDULE						DATE: 27-Nov-24			
LOCATION	STATIONS	NBN CO. CONDUIT LENGTH (m)				X-SECTION (m)		DRAW	KERB	REMARKS		
LOCATION	FROM - TO	50mm	No	100mm	No	EXCAVATION	PLUGS	WIRE	MARK	REWARKS		
BUSHMAN CT	1A - 12			17	1	17	2	19	2	CIVIL CONTRACTOR TO SUPPLY & INSTALL CROSS ROAD CONDUITS		
FLINDERS ST	2A - 2B	22	1			22	2	24	2	CIVIL CONTRACTOR TO SUPPLY & INSTALL CROSS ROAD CONDUITS		
	4 - 4A	20	1			20	2	22	2	CIVIL CONTRACTOR TO SUPPLY & INSTALL CROSS ROAD CONDUITS		
	5 - 5A	22	1			22	2	24	2	CIVIL CONTRACTOR TO SUPPLY & INSTALL CROSS ROAD CONDUITS		
	6 - 6A	24	1			24	2	26	2	CIVIL CONTRACTOR TO SUPPLY & INSTALL CROSS ROAD CONDUITS		
	7 - 7A	26	1			26	2	28	2	CIVIL CONTRACTOR TO SUPPLY & INSTALL CROSS ROAD CONDUITS		
	8 - 9	28	1			28	2	30	2	CIVIL CONTRACTOR TO SUPPLY & INSTALL CROSS ROAD CONDUITS		
TOTAL CIVIL		142		17		159	14	173	14			





WARNING

WARNING

POSSIBLE LIVE UNDERGROUND

ELECTRICAL CABLES ON THIS WORK SITE.

## WARNING: CIVIL CONTRACTOR

CHECK COMMUNICATIONS CONDUITS AND PITS ARE INSTALLED PRIOR TO CONSTRUCTING ANY RETAINING WALLS, PATHS, DRIVEWAYS AND WATER SERVICES

PRELIMINARY AWAITING NBN Co. APPROVAL



							STRICTLY CONFIDE	NTIAL	
							NBNCO APPROVAL RECORD: SIGNATURE DD	DATE	
							WD		
							OUALITY RECORD :  NBNCO DISCLAIMER THIS DOCUMENT HAS BEEN PREPARED SOLEL		
- REV	12-02-25 DATE	N.A.	)RAFTER	ORIGINAL ISSUE	N	APPROVED	NBNCO LIMITED (ABN 86 136 533 74.1) FOR USE IN MAINTAINING NBNCO FACILITIES. IT HAS NOT BEEN CREATED FOR ANY OTHER USE. IT SHOULD NOT BE SCALED TO LOCATE NBNCO ASSETS. NO WARRANTY IS GIVEN THAT THE INFORMATION IS ACCURATE OR COMPLETE.		
3				4	5	6	7		8



Electrical Contractors & Engine Campbell Ave Wacol Ph:(07)3271 2911

Job No: P.0551355.D.01

STAGE 1 STAGE 2 STAGE 4 STAGE 5 FS

OF 3